

Wastewater Collection Pipe Rehabilitation (CIPP)



Circular Road Project



Grand Falls · Windsor
| perfectly centered |

Outline

- Town Infrastructure
- History of Cured-In-Place-Pipe (CIPP)
- Advantages and Disadvantages
- CIPP vs. Traditional Replacement
- Scope of Work
- CIPP Process
- Project Challenges
- Conclusions

Town Infrastructure

10 Year Capital Spending Avg.

Running Annual Avg. Expenditure	
Roads	\$ 2,283,624
Water & Sewer	\$ 3,303,208
Recreation	\$ 844,703
Buildings	\$ 816,366
Average:	\$7,247,901

70-year replacement timeframe
Own approx. 97 km of sewer mains

Total Asset Replacement Value

Asset Class	Replacement Value (\$)	Portion of Total* Replacement Value (%)
Roads	146,725,782	29%
Facilities	135,885,036	27%
Sanitary	73,150,956	14%
Water	61,666,094	12%
Storm	49,024,141	10%
Equipment	26,885,662	5%
Parks and Land Improvements	8,949,725	2%
Fleet	2,560,857	1%
Total*	504,848,253	

History of CIPP

- Definition – *“Insertion of a resin-impregnated lining tube which is then cured to form a tight fit against the existing sewer.”*¹
- Invented in the early 1970 by Eric Wood
- 1st project – London 1971 (53 yrs.). 1,170 mm x 600 mm brick egg shaped sewer lined 6 mm.
- It is still in use today. Testing completed 20 & 30 years after install. Still in excellent shape.



Grand Falls Windsor
| perfectly centered |

History of CIPP

- 1st UK patent (Insituform) – August 21st, 1970
- 1st CIPP lining in NA was 300 mm drain in Fresno, CA in 1976.
- Formal design processes established in 1983.
- Design life = minimum of 50 years.
- Major installation in Winnipeg, MB in 1978
 - Assessed in 2003 and tested 2011 (450 mm liner)
 - Physicals like new

Advantages & Disadvantages

- Advantages:
 - Less residential disturbance (min. excavation)
 - Cheaper (depending on situation)
 - Thin-walled (flow capacity not compromised)
 - Minimal insertion access required
 - Ability to be pulled through bends
- Disadvantages:
 - Resin smell during steam curing
 - Complexity of installation

CIPP vs. Traditional Replacement

Traditional (Open Cut)

- 2,420 m of new mains.
- 1,320 m of service lines.
- 165 homes to be serviced.
- Approx. Cost = \$800/m
- Total = \$1,930,000 (est.)
 - Significant disturbance to the area. Only patching asphalt.
 - Homes serviced from rear.
 - Topography an issue.

CIPP Relining

2,347 m of sanitary mains relined.

173 m of 100 mm

2,074 m of 150 mm

100 m of 200 mm

106 services reinstated

Average Cost = \$601/m


Total = \$1,410,000

Existing Alignment Example




Elevations Table

Number	Minimum Elevation	Maximum Elevation	Area	Color
1	44.00	46.00	991.72	
2	46.00	48.00	9503.14	
3	48.00	50.00	16837.02	
4	50.00	52.00	68965.99	
5	52.00	54.00	45019.35	
6	54.00	56.00	18310.69	
7	56.00	58.00	13787.18	
8	58.00	60.00	13088.59	
9	60.00	62.00	3708.72	
10	62.00	64.00	2009.72	
11	64.00	66.00	2482.81	
12	66.00	68.00	2038.01	
13	68.00	70.00	2155.44	
14	70.00	72.00	2777.16	
15	72.00	74.00	5015.81	
16	74.00	76.00	2256.97	
17	76.00	78.00	13.90	



CIPP Scope of Work



Project Description

- Project funded under ICIP – 17-GI-22-00034
- Total funding was \$3,489,067 HST included
 - Water, storm and CIPP sanitary repairs in the Circular Road area. Work remaining for 2024.
 - 90-year-old clay sewer lines
 - Project broken into three separate tenders and a PCA for engineering services.
 - AllNorth Consulting - \$83,000
 - Afonso Contracting - \$1,410,000
 - ANW Contracting - \$1,008,000
 - Paving - \$265,000

CIPP Process

- Clean & complete CCTV of existing pipe
- Clean host pipe – remove root intrusion, grease, debris buildup and trim services.
- Setup bypass for flow & communication
- Install CIPP liner – pull-in-place or inversion
- Cure the CIPP – steam, hot water or UV light
- Reinstate the service connections
- CCTV camera of final product & QA samples
- CCTV 1-year warranty inspection

Camera Equipment



CCTV Pre-Inspection



CCTV Pre-Inspection



CCTV Pre-Inspection



Design – Fully Deteriorated

PROGRESSIVE ENGINEERING & CONSULTING

CIPP-DESIGN

CIPP Liner Thickness for Non-Pressure Pipes
By ASTM F1216-16 Appendix X1 Design Method

PROJECT INFORMATION MH 531 to MH 577 Section 1	Design Date: Jul 13, 2023	<p>Ground Surface</p> <p>1.88 m 1.73 m 1.50 m</p> <p>Obvert Water Table</p> <p>0.38 m</p> <p>Invert Invert</p> <p>Existing Pipe: 150 mm ID; Ovality: 3% Fully Deteriorated Design Required Liner Thickness: 2.5 mm</p>
---	---------------------------	--



- Required ASTM F1216-16 Appendix X-1 Design
- Fully Deteriorated
- 50-year design life
- Majority 2.5 mm liners
- Flow capacity
- ~20-30% thicker liner compared to partially deteriorated design.

EXISTING PIPE PARAMETERS	ENTERED	CIPP liner design by Appendix X1 method of ASTM F1216-16
Existing Pipe Condition	Fully Det.	KEY FACTORS: FULLY DETERIORATED CONDITION DESIGN
Inside Diameter, D	150 mm	Flexural Modulus, E, 50 Year Design
Depth to Invert	1.88 m	Flexural Strength, σ , 50 Year Design
Water Table below Surface	1.5 m	Minimum Dia for host pipe
Ovality of Existing Pipe, Δ	3%	Maximum Dia for host pipe
Soil Density, w (2000 Kg/m ³)	19.61 KN/m ³	Ovality Reduction Factor, C
Soil Modulus, E's	6.9 MPa	Water Buoyancy Factor, R _w
Live Load Used	HS-20	Coeff of Elastic Support, B'
Other Load	0 kPa	Water Pressure, Invert
CIPP LINER PARAMETERS	ENTERED	Total Design Pressure, P, Invert
Design Life	50 Years	Water Pressure, Obvert
Flexural Modulus Short-term Test, E _s	1724 MPa	Soil Pressure, Obvert
% of E _s used for 50 Year Design E	50%	Live Load Pressure W _s , Obvert
Flexural Strength Short-term Test, σ_s	31 MPa	Other Load Pressure, Obvert
% of σ_s used for 50 Year Design σ	50%	Total Design Pressure, q _t , Obvert
Enhancement Factor, K	7	NOTES: E and σ correspond with E ₁ and σ_1 in F1216 Appendix X1
Poisson's Ratio, ν	0.3	Note 1: AASHTO HS-20. Refer AWWA M11, M23, M55.
Safety Factor, N	2	Note 2: t based on providing DR \leq 100. See F1216 Note X1.2

DESIGN BY ASTM F1216 VERSION			
F1216-16			
FULLY DETERIORATED DESIGN REQUIRES CIPP THICKNESS SATISFY F1216-X1 EQUATIONS X1.1, X1.2, X1.3 & X1.4			
Equation	Required t mm	Required t in	Required DR
X1.1: $P = [2KE/(1-\nu^2)] \times [1/(DR-1)^3] \times [C/N]$	1.5 mm	0.059 in	100.0
For load at invert due to groundwater hydrostatic pressure	Note 2	Note 2	Note 2
X1.2: $(1.5\Delta/100)(1+\Delta/100)(DR)^2-0.5(1+\Delta/100)DR=\sigma/(PN)$	0.7 mm	0.028 in	214.3
For minimum thickness for ovality			
X1.3: $qt=[1/N] \times [32 \times R_w \times B' \times E_s \times C \times (E \times I/D^3)]^{1/2}$	2.1 mm	0.083 in	71.4
For load at obvert due to groundwater, soil & live loads			
X1.4: $(E_s \times I)/D^3 \geq Es/[12(DR^3)] \geq 0.00064$	Governs	2.5 mm	0.098 in
For minimum CIPP liner stiffness			
Required in Place Liner Thickness - Fully Deteriorated	2.5 mm	0.098 in	60.0
t mm is rounded-up to 1 decimal place; t in = t mm/25.4; DR = (Inside Diameter mm)/(t mm) NA - Not Available/Applicable			
Liner Sample Test Requirements Are: E _s \geq 1724 MPa (ASTM D790); σ_s \geq 31 MPa (ASTM D790); Thickness \geq 2.5 mm (ASTM D5813). If test results are at variance, other combinations of properties and thickness can provide required liner performance. Reconcile design.			
PARAMETERS FOR FLOW COMPARISON		FLOW COMPARISON FOR 2.5 mm LINER	
Liner thickness for flow comparison	2.5 mm	Inside Diameter before Lining	150 mm
Manning n used for before lining	0.0120	Inside Diameter after Lining	145 mm
Manning n used for after lining	0.0100	Flow Capacity after Lining	110% of before lining flow

COMMENTS

Heavy Root Intrusion



Root Cutting Equipment



Pull in Place & Inversion



Hot Water Curing



Hot Water Curing

- All 100 mm pipes were wetted with epoxy on-site and cured with hot water.
- Epoxy lining designed for shorter runs (~50m)
- 1-3 hour curing time
- Disadvantage is they must be used installed and cured quickly.

Steam Curing



Steam Curing



Steam Curing

- Liners were ordered from New Jersey already pre-wetted with resin and kept on ice.
- Kept in refrigeration truck out of sunlight.
- Curing is 90 minutes at 130 degrees Fahrenheit with 30-minute cool down.
- Pressure varies 8 – 12 psi.
- 3 thermocouples in place measuring temps.

Reinstate Service Connections



REINSTATEMENT CUTTER

CCTV Camera (Post)



CCTV Camera (Post)

m/h 1282 to m/h 578 post liner

10:02:32AM 2023/10/28

26.2M


CCTV Camera (Post)



QA Testing



QA Testing



— Specimen 1 — Specimen 2 — Specimen 3
— Specimen 4 — Specimen 5



QA Testing



LABORATORY REPORT

Paragon Systems Testing
 18 Basaltic Road
 Concord Ontario, Canada, L4K 1G6
 Tel: (905) 738-0447 Fax: (905) 738-565

TS 4.10 Liner Sample Test Results - Reconciliation and Deficiency Evaluation Matrix

Test Results	Units	Test Results (from page 1)	Properties Required per Design (Note 1,3)	Test Results vs Design	Required Thickness At Test Properties (RTATP) (Note 2, 3)	Reconciliation Outcome
Short Term Flexural Modulus	MPa	1,780	1,720	Acceptable	—	None
Short Term Flexural Strength	MPa	48.4	31.0	Acceptable	—	None
Thickness (avg)	mm	3.2	2.5	Acceptable	—	None
Thickness (min)	mm	2.9	2.2	Acceptable	—	None
Overall Sample Status						NOT DEFICIENT

Project Challenges

- Resin curing - smell complaints (plastic).
- ~2% homes had toilet issue during cleaning.
- 13 pits (distance, size change or joint offsets).
- Small manholes and site access difficult.
- Sags too great in three locations to complete.
- Roots excessive in one line.
- One line with protruding cast iron services.
- One liner failed resulting in sewer backup.

Conclusion

- Approx. 165 homes with relined sewer main.
- Approx. 2.4 km of rehabilitated infrastructure.
- Challenges encountered but successful project
- QA testing results were satisfactory.
- Experienced gained by Town staff.
- Significantly lower disturbance option.
- Contractor great to work with.