

Government of Newfoundland and Labrador Department of Environment, Climate Change and Municipalities Water Resources Management Division

PERMIT TO ALTER A BODY OF WATER

Pursuant to the Water Resources Act, SNL 2002 cW-4.01, specifically Section(s) 48

Date:	JANUARY 14, 2021	File No: <u>533-04</u> Permit No: <u>ALT11574-2021</u>
Permit Holder:	Corner Brook Pulp & Paper Ltd. P.O. Box 2001 Corner Brook, NL A2H 6J4 kevin.robertson@kruger.com	
Attention:	Kevin Robertson	
Re:	Various Bodies of Water - Stream Crossings - Bla	anket Permit

Permission is hereby given for : stream crossing projects that require one culvert (not greater than 2000mm diameter), a bridge with a maximum span of 5m, or fording at various water bodies located outside designated protected water supply areas to facilitate the installation of culverts, bridges and fordings during Permit Holder's operating seasons, with reference to the application dated November 12, 2020.

- This Permit does not release the Permit Holder from the obligation to obtain appropriate approvals from other concerned municipal, provincial and federal agencies.
- The Permit Holder must obtain the approval of the Crown Lands Administration Division if the project is being carried out on Crown Land.
- This Permit is subject to the terms and conditions indicated in Appendices A and B (attached).
- It should be noted that prior to any significant changes in the design or installation of the proposed works, or in event of changes in ownership or management of the project, an amendment to this Permit must be obtained from the Department of Environment, Climate Change and Municipalities under Section 49 of the *Water Resources Act*.

(for) MINISTER

GOVERNMENT OF NEWFOUNDLAND AND LABRADOR Department of Environment, Climate Change and Municipalities

File No: <u>533-04</u> Permit No: ALT11574-2021

APPENDIX A

Terms and Conditions for Permit

Special Conditions

- 1. The Permit Holder must apply for and obtain a separate permit under the Water Resources Act, SNL 2002 cW-4.01, specifically Section 39 https://assembly.nl.ca/Legislation/sr/statutes/w04-01.htm for any stream crossing project within any designated Protected Public Water Supply Area servicing any community as indicated in Water Resources Portal available at https://maps.gov.nl.ca/water/mapbrowser/Default.aspx.
- 2. The Permit Holder must apply for and obtain a separate permit under the Water Resources Act, SNL 2002 cW-4.01, specifically Section 48 https://assembly.nl.ca/Legislation/sr/statutes/w04-01.htm for any stream crossing project within any designated flood risk area as indicated at https://www.gov.nl.ca/eccm/waterres/flooding/frm/
- 3. The Permit Holder must apply for and obtain a separate permit under the Water Resources Act, SNL 2002 cW-4.01, specifically Section 48 https://assembly.nl.ca/legislation/sr/statutes/w04-01.htm for the installation of any culvert, bridge, and/or fording that may take place within any municipal boundary.
- 4. The crossing structure must provide adequate capacity to safely discharge flood flows without causing backwater effects upstream and increased flow velocity downstream.
- 5. For any stream crossing project carried out under this Permit, the Permit Holder must notify this Department via email to waterinvestigations@gov.nl.ca or facsimile at (709)729-0320 in accordance with a reporting protocol as deemed necessary and appropriate in the opinion of the Minister. Also, any stream crossing project carried out under this Permit shall be subject to the payment of applicable fee by the Permit Holder as stated in the application fee schedules approved by the Minister.
- 6. The Permit Holder acknowledges and agrees that this Permit may require and will be amended to include further provisions pursuant to the Water Resources Act, SNL 2002 cW-4.01 and its regulations and policies in effect thereunder from time to time, as deemed necessary in the opinion of the Minister.
- 7. A water quality monitoring program is not required at this time. However, this Department reserves the right to require that the Permit Holder sample, analyse, and submit results of water quality tests, for the purpose of ensuring that the water quality is maintained within acceptable guidelines. All analyses must be undertaken by a CALA accredited laboratory. Also, this Department reserves the right to require that the Permit Holder set-up monitoring stations through a Memorandum of Agreement under the Water Resources Act, SNL 2002 cW-4.01 and its regulations and policies in effect thereunder from time to time, as deemed necessary in the opinion of the Minister.
- 8. Corner Brook Pulp and Paper Ltd. (Kruger) Standard Operating Procedures for Deactivating Roads and Stream Crossings and Open-Bottomed Structures for Large Crossings shall be followed in conjunction with the Terms and Conditions of this Permit.
- 9. Annually (at the end of the year), the permit holder is required to submit a work done report under this permit along with the applicable fees incurred during the period.

Culvert Installation

10. Drainage ditches must collect and transport surface runoff in a manner that does not cause flooding, erosion or sedimentation of adjacent land or receiving waters.

- 11. Inlet and outlet areas of culvert installations must be adequately protected from erosion by placing rip-rap, fitted stone, or concrete headwalls.
- 12. Culvert installations must follow the stream channel gradient to the maximum extent possible and placed in line with the direction of the main flow to minimize disturbance to the channel. Culverts must not disrupt the flow of water or cause ponding at the upstream side of the installation.
- 13. In multiple culvert installations, one culvert must be set a minimum of 150 mm lower than the others to provide adequate water depth and velocity for fish passage during low flow conditions. In addition, multiple culverts must be installed within 0.6 to 0.9 metres apart for maximum stability.
- 14. Where pumping is used to bypass flow, cofferdams must be installed both above and below areas of construction. The Permit Holder must provide pumps with sufficient capacity to prevent washout of cofferdams.
- 15. Cofferdams must be properly designed and constructed of suitable materials to prevent leakage and to resist loss of any material as a result of erosion. Cofferdams must be removed upon completion of their intended function. All material must be removed carefully to prevent disturbance of the water body and to prevent water quality degradation.
- 16. All work involving minor alteration to the stream channel to permit culvert placement must be carried out at a time of low flow, and in a manner that prevents downstream siltation and unnecessary alteration of the channel.
- 17. Grading and finishing of roadways or road embankments must not cause damage to culverts or allow road material to enter the watercourse.
- 18. Roadside embankments near the watercourse must be adequately protected from erosion by sodding, seeding or placing of rip-rap.
- 19. Culverts must be inspected regularly so that immediate action can be taken to clear blockages caused by ice or debris or to undertake repairs as required.
- 20. The inlet and outlet of culverts must be clearly marked so that operators of road grading and snow clearing equipment can avoid blocking culverts.
- 21. Any damage to culverts during installation or due to inadequate capacity and/or improper construction must be reported to this Department. Damaged culverts must be replaced immediately to prevent overtopping, erosion, or flooding.
- 22. If a culvert is installed in natural fish habitat it must be embedded a minimum of 150 mm below the natural streambed (up to a maximum of 1/3 of the culvert diameter).

Bridge Construction

- 23. The use of creosote treated wood is strictly prohibited within 15 metres of all bodies of fresh water in the province.
- 24. Drainage ditches must collect and transport surface runoff in a manner that does not cause flooding, erosion or sedimentation of adjacent land or receiving waters.
- 25. Bridge abutments must be set back 0.5 metres from the normal edge of a watercourse to prevent constriction during high flow conditions.

- 26. Infilling must not cause increased water elevation upstream or increase flow velocity downstream of the site. Reduction of the natural cross sectional area of any watercourse is not permitted.
- 27. The upstream and downstream sides of abutments must be protected with rip-rap, concrete or heavy timber to prevent erosion and scouring.
- 28. Where pumping is used to bypass flow, cofferdams must be installed both above and below areas of construction. The Permit Holder must provide pumps with sufficient capacity to prevent washout of cofferdams.
- 29. Cofferdams must be properly designed and constructed of suitable materials to prevent leakage and to resist loss of any material as a result of erosion. Cofferdams must be removed upon completion of their intended function. All material must be removed carefully to prevent disturbance of the water body and to prevent water quality degradation.
- 30. Abutments and piers must be constructed in the dry and during times of low flow.
- 31. Roadside embankments near the watercourse must be adequately protected from erosion by sodding, seeding or placing of rip-rap.
- 32. Adequate erosion protection must be provided where roadside ditches discharge into watercourses near bridges.

Fording

- 33. Except for single passenger all-terrain vehicles, crossings by other vehicles or construction equipment shall be limited to one trip in and one trip out.
- 34. Timbers or rocks shall be placed in streams to facilitate crossing or to minimize damage to the channel sections provided the streams are not unnecessarily constricted or backed up.
- 35. Alteration of the natural minimum streamflow is not permitted in order to preserve aquatic life.
- 36. Stream banks at fording sites that contain loose or erodible material must be adequately stabilized before crossing to minimize any siltation of streams.
- 37. The natural course of any stream must not be altered.
- 38. Infilling must not cause increased water elevation upstream or increase flow velocity downstream of the site. Reduction of the natural cross sectional area of any watercourse is not permitted.
- 39. The fording sites must be located at shallow sections of the channels where there are low approach grades, and where the channels consists of stable non-erodible rock or cobbles.
- 40. Fording shall only be carried out during periods of low water levels.
- 41. When the fording sites are no longer required, the Permit Holder must dismantle and remove all constructed works and restore the sites to their original condition. All material placed in streams must be completely removed.

- 42. A complete oil spill clean-up kit must be on site at all times when gasoline or fuel powered equipment is being used or refuelled. The kit must contain the following:
 - One hand operated fuel pump
 - One recovery container such an empty 205 litre drum
 - One shovel
 - One pick axe
 - Five metres of containment boom
 - Five absorbent pads
 - Twenty-five litres of loose absorbent material
- 43. Within 30 days after expiry of this Permit, the Permit Holder must submit to the department a report confirming that each fording location was left in as good or better condition than prior to Permit Holder's fording activities. This report should include detailed pictures of each site before and after project activities.

General Alterations

- 44. Any work that must be performed below the high water mark must be carried out during a period of low water levels.
- 45. Any flowing or standing water must be diverted around work sites so that work is carried out in the dry.
- 46. Water pumped from excavations or work areas, or any runoff or effluent directed out of work sites, must have silt and turbidity removed by settling ponds, filtration, or other suitable treatment before discharging to a body of water. Effluent discharged into receiving waters must comply with the *Environmental Control Water and Sewage Regulations, 2003.*
- 47. All operations must be carried out in a manner that prevents damage to land, vegetation, and watercourses, and which prevents pollution of bodies of water.
- 48. The use of heavy equipment in streams or bodies of water is not permitted. The operation of heavy equipment must be confined to dry stable areas.
- 49. All vehicles and equipment must be clean and in good repair, free of mud and oil, or other harmful substances that could impair water quality.
- 50. During the construction of concrete components, formwork must be properly constructed to prevent any fresh concrete from entering a body of water. Dumping of concrete or washing of tools and equipment in any body of water is prohibited.
- 51. Wood preservatives such as penta, CCA or other such chemicals must not be applied to timber near a body of water. All treated wood or timber must be thoroughly dry before being brought to any work site and installed.
- 52. Any areas adversely affected by this project must be restored to a state that resembles local natural conditions. Further remedial measures to mitigate environmental impacts on water resources can and will be specified, if considered necessary in the opinion of this Department.
- 53. The bed, banks and floodplains of watercourses, or other vulnerable areas affected by this project, must be adequately protected from erosion by seeding, sodding or placing of rip-rap.
- 54. All waste materials resulting from this project must be disposed of at a site approved by the Department of Digital Government and Service NL.

- 55. Periodic maintenance such as painting, resurfacing, clearing of debris, or minor repairs, must be carried out without causing any physical disruption of any watercourse. Care must be taken to prevent spillage of pollutants into the water.
- 56. The owners of structures are responsible for any environmental damage resulting from dislodgement caused by wind, wave, ice action, or structural failure.
- 57. Sediment and erosion control measures must be installed before starting work. All control measures must be inspected regularly and any necessary repairs made if damage is discovered.
- 58. Fill material must be of good quality, free of fines or other substances including metals, organics, or chemicals that may be harmful to the receiving waters.
- 59. The attached Completion Report (Appendix C) for Permit No. 11574 must be completed and returned to this Department upon completion of the approved works. Pictures must be submitted along with the completion report, showing the project site prior to and after development.
- 60. This Permit is effective from January 14, 2021 and shall expire on January 14, 2023 or earlier if modified, suspended or cancelled by the Minister. Also, this Permit may be renewed by the Minister for such renewal term as the Minister deems appropriate, on such terms and conditions as the Minister considers appropriate and in the public interest, provided the Permit Holder applies for the renewal at least ninety (90) days before the expiry of this Permit.
- 61. All work must be carried out within the Permit Holder's legal property boundaries.
- 62. Except as stated in Clause #33 under **FORDING**, the use of heavy equipment in streams or bodies of water is not permitted. The operation of heavy equipment must be confined to dry stable areas.

GOVERNMENT OF NEWFOUNDLAND AND LABRADOR Department of Environment, Climate Change and Municipalities

File No: <u>533-04</u> Permit No: ALT11574-2021

APPENDIX B

Special Terms and Conditions for Permit

- 1. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall keep all systems and works in good condition and repair and in accordance with all laws, by-laws, directions, rules and regulations of any governmental authority. The Permit Holder or its agent(s), subcontractor(s), or consultant(s) shall immediately notify the Minister if any problem arises which may threaten the structural stability of the systems and works, endanger public safety and/or the environment or adversely affect others and/or any body of water either in or outside the said Project areas. The Permit Holder and its agent(s), subcontractor (s), and consultant(s) shall be responsible for all damages suffered by the Minister and Government resulting from any defect in the systems and works, operational deficiencies/inadequacies, or structural failure.
- 2. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall operate the said Project and its systems and works in a manner which does not cause any water related and/or environmental problems, including but not limited to problems of erosion, deposition, flooding, and deterioration of water quality and groundwater depletion, in or outside the said Project areas. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall be responsible for any and all damages associated with these problems caused as a result of changes, deficiencies, and inadequacies in the operational procedures by the Permit Holder or its agent(s), subcontractor(s).
- 3. If the Permit Holder or its agent(s), subcontractor(s), or consultant(s) fails to perform, fulfil, or observe any of the terms and conditions, or provisions of this Permit, as determined by this Department, the Minister may, without notice, amend, modify, suspend or cancel this Permit in accordance with the *Water Resources Act.*.
- 4. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) indemnify and hold the Minister and Government harmless against any and all liabilities, losses, claims, demands, damages or expenses including legal expenses of any nature whatsoever whether arising in tort, contract, statute, trust or otherwise resulting directly or indirectly from granting this Permit, systems and works in or outside the said Project areas, or any act or omission of the Permit Holder or its agent(s), subcontractor(s), or consultant(s) in or outside the said Project areas, or arising out of a breach or non-performance of any of the terms and conditions, or provisions of this Permit by the Permit Holder or its agent(s), subcontractor(s), or consultant(s).
- 5. This Permit is subject to all provisions of the *Water Resources Act* and any regulations in effect either at the date of this Permit or hereafter made pursuant thereto or any other relevant legislation enacted by the Province of Newfoundland and Labrador in the future.
- 6. This Permit shall be construed and interpreted in accordance with the laws of the Province of Newfoundland and Labrador.

- cc: Jeff Bannister (Western and Labrador) Western and Labrador Regional Lands Manager Crown Lands Administration Division Department of Fisheries, Forestry and Agriculture JeffBannister@gov.nl.ca
- cc: Fisheries Protection Division Ecosystem Management Branch Fisheries and Oceans Canada P.O. Box 5667 St. John's, NL A1C 5X1 FPP-NL@dfo-mpo.gc.ca
- cc: Amir Ali Khan, Ph.D., P.Eng. Manager, Water Rights, Investigations and Modelling Section Water Resources Management Division Department of Environment, Climate Change and Municipalities P.O. Box 8700 4th Floor, West Block, Confederation Building St. John's, NL A1B 4J6 akhan@gov.nl.ca



Government of Newfoundland and Labrador Department of Environment, Climate Change and Municipalities Water Resources Management Division

Appendix C - Completion Report

Pursuant to the Water Resources Act, SNL 2002 cW-4.01, specifically Section(s) 48

Date: **JANUARY 14, 2021**

File No: <u>533-04</u> Permit No: <u>ALT11574-2021</u>

Permit Holder: Corner Brook Pulp & Paper Ltd. P.O. Box 2001 Corner Brook, NL A2H 6J4 kevin.robertson@kruger.com

Attention: Kevin Robertson

Re: Various Bodies of Water - Stream Crossings - Blanket Permit

Permission was given for : stream crossing projects that require one culvert (not greater than 2000mm diameter), a bridge with a maximum span of 5m, or fording at various water bodies located outside designated protected water supply areas to facilitate the installation of culverts, bridges and fordings during Permit Holder's operating seasons, with reference to the application dated November 12, 2020.

I (the Permit Holder named above or agent authorized to represent the Permit Holder) do hereby certify that the project described above was completed in accordance with the plans and specifications submitted to the Department of Environment, Climate Change and Municipalities and that the work was carried out in strict compliance with the terms and conditions of the Permit issued for this project.

Date:

Signature:

This completion report must be completed and forwarded to the following address upon completion of the approved work.

Department of Environment, Climate Change and Municipalities Water Resources Management Division PO Box 8700 St. John's NL A1B 4J6