

Government of Newfoundland and Labrador Department of Environment and Climate Change Water Resources Management Division

PERMIT TO ALTER A BODY OF WATER

Pursuant to the Water Resources Act, SNL 2002 cW-4.01, specifically Section(s) 48

Date: **FEBRUARY 04, 2022** File No: <u>524</u>

Permit No: <u>ALT12313-2022</u>

Permit Holder: **Bay Bulls Properties Ltd.**

650 Water Street PO Box 1083

St. John's, NL A1C 5M5 dhiraj.kc@pennecon.com

Attention: **Dhiraj KC**

Re: Bay Bulls Harbour - Infilling and Wharf Construction

Permission is hereby given for: the infilling of approximately 343 cubic metres of rock and approximately 30 cubic metres of rip rap within Bay Bulls Harbour within the Town of Bay Bulls for the construction of a rockfill approach and a 17.2 by 3.7 m timber crib commercial grade wharf, in reference to the application received on January 20, 2022, and additional information received on January 24, 2022 and on February 3, 2022.

- This Permit does not release the Permit Holder from the obligation to obtain appropriate approvals from other concerned municipal, provincial and federal agencies.
- The Permit Holder must obtain the approval of the Crown Lands Administration Division if the project is being carried out on Crown Land.
- This Permit is subject to the terms and conditions indicated in Appendices A and B (attached).
- It should be noted that prior to any significant changes in the design or installation of the proposed works, or in event of changes in ownership or management of the project, an amendment to this Permit must be obtained from the Department of Environment and Climate Change under Section 49 of the *Water Resources Act*.

(for) MINISTER

GOVERNMENT OF NEWFOUNDLAND AND LABRADOR

Department of Environment and Climate Change

File No: **524**

Permit No: ALT12313-2022

APPENDIX A

Terms and Conditions for Permit

Infilling

- 1. The slopes along the perimeter of infilled areas must be no steeper than two horizontal to one vertical (2H:1V).
- 2. The constructed works must be inspected regularly so that action can be taken to undertake repairs as required.
- 3. Fill material must be obtained from an approved quarry site. It must not be taken from beaches or streams, and must not be dredged from a body of water.
- 4. The natural course of any stream must not be altered.
- 5. Infilling must not cause increased water elevation upstream or increase flow velocity downstream of the site. Reduction of the natural cross sectional area of any watercourse is not permitted.
- 6. Infilling must not disrupt the established surface drainage pattern of the area.
- 7. Infilling must not cause increased water elevation upstream or increase flow velocity downstream of the site.
- 8. Before infilling, any vegetation and topsoil must be completely removed and under no circumstances shall it be used as fill material. Topsoil must be stored and reused in final landscaping of the infilled area.
- 9. The constructed works must comply with all other terms and conditions provided in the Crown Lands grant, lease, or license for occupancy.
- 10. Select heavy rocks must be placed along the toe of any infilling to provide slope stability and erosion protection.

Wharf/Slipway

- 11. Armour stone must be placed around cribbing, where required, to prevent erosion.
- 12. Suitable booms must be deployed around construction sites to contain any floating debris that might otherwise be carried away. All booms must be properly maintained and remain in place until all work is completed.
- 13. The wharf / dock must be constructed in accordance with this department's *Environmental Guidelines* for Construction and Maintenance of Wharves, Breakwaters, Slipways and Boathouses located on the departmental website:
 - http://www.env.gov.nl.ca/env/waterres/regulations/appforms/Guidelines_for_Wharves.pdf

General Alterations

- 14. Any work that must be performed below the high water mark must be carried out during a period of low water levels.
- 15. Any flowing or standing water must be diverted around work sites so that work is carried out in the dry.
- 16. Water pumped from excavations or work areas, or any runoff or effluent directed out of work sites, must have silt and turbidity removed by settling ponds, filtration, or other suitable treatment before discharging to a body of water. Effluent discharged into receiving waters must comply with the *Environmental Control Water and Sewage Regulations*, 2003.
- 17. All operations must be carried out in a manner that prevents damage to land, vegetation, and watercourses, and which prevents pollution of bodies of water.
- 18. The use of heavy equipment in streams or bodies of water is not permitted. The operation of heavy equipment must be confined to dry stable areas.
- 19. All vehicles and equipment must be clean and in good repair, free of mud and oil, or other harmful substances that could impair water quality.
- 20. Wood preservatives such as penta, CCA or other such chemicals must not be applied to timber near a body of water. All treated wood or timber must be thoroughly dry before being brought to any work site and installed.
- 21. Any areas adversely affected by this project must be restored to a state that resembles local natural conditions. Further remedial measures to mitigate environmental impacts on water resources can and will be specified, if considered necessary in the opinion of this Department.
- 22. The bed, banks and floodplains of watercourses, or other vulnerable areas affected by this project, must be adequately protected from erosion by seeding, sodding or placing of rip-rap.
- 23. All waste materials resulting from this project must be disposed of at a site approved by the Department of Digital Government and Service NL.
- 24. Periodic maintenance such as painting, resurfacing, clearing of debris, or minor repairs, must be carried out without causing any physical disruption of any watercourse. Care must be taken to prevent spillage of pollutants into the water.
- 25. The owners of structures are responsible for any environmental damage resulting from dislodgement caused by wind, wave, ice action, or structural failure.
- 26. Sediment and erosion control measures must be installed before starting work. All control measures must be inspected regularly and any necessary repairs made if damage is discovered.
- 27. Fill material must be of good quality, free of fines or other substances including metals, organics, or chemicals that may be harmful to the receiving waters.
- 28. The attached Completion Report (Appendix C) for Permit No. 12313 must be completed and returned to this Department upon completion of the approved works. Pictures must be submitted along with the completion report, showing the project site prior to and after development.

- 29. This Permit is valid for two years from the date of issue. Work must be completed by that date or the application and approval procedure must be repeated.
- 30. The location of the work is highlighted on the Location Map for this Permit attached as Appendix D.

GOVERNMENT OF NEWFOUNDLAND AND LABRADOR

Department of Environment and Climate Change

File No: **524**

Permit No: ALT12313-2022

APPENDIX B

Special Terms and Conditions for Permit

- 1. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall keep all systems and works in good condition and repair and in accordance with all laws, by-laws, directions, rules and regulations of any governmental authority. The Permit Holder or its agent(s), subcontractor(s), or consultant(s) shall immediately notify the Minister if any problem arises which may threaten the structural stability of the systems and works, endanger public safety and/or the environment or adversely affect others and/or any body of water either in or outside the said Project areas. The Permit Holder and its agent(s), subcontractor (s), and consultant(s) shall be responsible for all damages suffered by the Minister and Government resulting from any defect in the systems and works, operational deficiencies/inadequacies, or structural failure.
- 2. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall operate the said Project and its systems and works in a manner which does not cause any water related and/or environmental problems, including but not limited to problems of erosion, deposition, flooding, and deterioration of water quality and groundwater depletion, in or outside the said Project areas. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall be responsible for any and all damages associated with these problems caused as a result of changes, deficiencies, and inadequacies in the operational procedures by the Permit Holder or its agent(s), subcontractor(s), or consultant(s).
- 3. If the Permit Holder or its agent(s), subcontractor(s), or consultant(s) fails to perform, fulfil, or observe any of the terms and conditions, or provisions of this Permit, as determined by this Department, the Minister may, without notice, amend, modify, suspend or cancel this Permit in accordance with the *Water Resources Act*.
- 4. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) indemnify and hold the Minister and Government harmless against any and all liabilities, losses, claims, demands, damages or expenses including legal expenses of any nature whatsoever whether arising in tort, contract, statute, trust or otherwise resulting directly or indirectly from granting this Permit, systems and works in or outside the said Project areas, or any act or omission of the Permit Holder or its agent(s), subcontractor(s), or consultant(s) in or outside the said Project areas, or arising out of a breach or non-performance of any of the terms and conditions, or provisions of this Permit by the Permit Holder or its agent(s), subcontractor (s), or consultant(s).
- 5. This Permit is subject to all provisions of the *Water Resources Act* and any regulations in effect either at the date of this Permit or hereafter made pursuant thereto or any other relevant legislation enacted by the Province of Newfoundland and Labrador in the future.
- This Permit shall be construed and interpreted in accordance with the laws of the Province of Newfoundland and Labrador.

File No: <u>**524**</u>

Permit No: <u>ALT12313-2022</u>

cc: Amir Ali Khan, Ph.D., P.Eng.

Manager, Water Rights, Investigations and Modelling Section Water Resources Management Division
Department of Environment and Climate Change
P.O. Box 8700
4th Floor, West Block, Confederation Building
St. John's, NL A1B 4J6
akhan@gov.nl.ca

cc: Frank Norman (Eastern)

Land Management Specialist Crown Lands Administration Department of Fisheries, Forestry and Agriculture Howley Building St. John's franknorman@gov.nl.ca

cc: Fisheries Protection Division

Ecosystem Management Branch Fisheries and Oceans Canada P.O. Box 5667 St. John's, NL A1C 5X1 FPP-NL@dfo-mpo.gc.ca

cc: Marine Safety

Transport Canada, Atlantic Regional Headquarters Airports, Harbours and Ports, and Environmental Services 95 Foundry St. P.O. Box 42 Moncton, NB E1C 8K6 NPPATL-PPNATL@tc.gc.ca

cc: Town of Bay Bulls

Ms. Janet O'Brien
2 Southside Road
P.O. Box 70
Bay Bulls, NL A0A 1C0
info@townofbaybulls.com



Government of Newfoundland and Labrador Department of Environment and Climate Change Water Resources Management Division

Appendix C - Completion Report

| Pursuant to th | ne Water Resources Act, SNL 2002 cW-4.0 | 01, specifically Section(s) 48 |
|------------------------------|---|---|
| Date: | FEBRUARY 04, 2022 | File No: <u>524</u> Permit No: ALT12313-2022 |
| Permit Hold | er: Bay Bulls Properties Ltd. 650 Water Street PO Box 1083 | 1 0 mm v 1 (o) 1 mm v 2 v 2 v 2 v 2 v 2 v 2 v 2 v 2 v 2 |
| | St. John's, NL A1C 5M5 dhiraj.kc@pennecon.com | |
| Attention: | Dhiraj KC | |
| Re: | Bay Bulls Harbour - Infilling and W | harf Construction |
| metres of rip approach an | o rap within Bay Bulls Harbour within the a 17.2 by 3.7 m timber crib commercia | ely 343 cubic metres of rock and approximately 30 cubic he Town of Bay Bulls for the construction of a rockfill al grade wharf, in reference to the application received eived on January 24, 2022 and on February 3, 2022. |
| certify specif | o that the project described above was com ications submitted to the Department of E arried out in strict compliance with the ter | horized to represent the Permit Holder) do hereby apleted in accordance with the plans and invironment and Climate Change and that the work cms and conditions of the Permit issued for this |

This completion report must be completed and forwarded to the following address upon completion of the approved work.

Department of Environment and Climate Change Water Resources Management Division PO Box 8700 St. John's NL A1B 4J6

GOVERNMENT OF NEWFOUNDLAND AND LABRADOR

Department of Environment and Climate Change

File No: <u>524</u> Permit No: <u>ALT12313-2022</u>

APPENDIX D **Location Map for Permit**

