

Government of Newfoundland and Labrador Department of Environment and Climate Change Water Resources Management Division

PERMIT TO ALTER A BODY OF WATER

Pursuant to the Water Resources Act, SNL 2002 cW-4.01, specifically Section(s) 48

Date: MARCH 24, 2023 File No: <u>526</u>

Permit No: **ALT12996-2023**

Permit Holder: Marathon Gold Corporation

7 Queensway

Grand Falls-Windsor

NL A2B 1K9

sfinlay@marathon-gold.com

Attention: Scott Finlay

Re: Valentine Gold Project (unnamed waterbody) - Installation of temporary water intake

system for concrete batch plant

Permission is hereby given for: the installation of a temporary water intake system (pump and 76.2 mm HDPE delivery pipe) in an unnamed waterbody for supplying water to concrete batch plant in Valentine Gold Project, with reference to the application dated February 23, 2023 and additional information received on March 24, 2023.

- This Permit does not release the Permit Holder from the obligation to obtain appropriate approvals from other concerned municipal, provincial and federal agencies.
- The Permit Holder must obtain the approval of the Crown Lands Administration Division if the project is being carried out on Crown Land.
- This Permit is subject to the terms and conditions indicated in Appendices A and B (attached).
- It should be noted that prior to any significant changes in the design or installation of the proposed works, or in event of changes in ownership or management of the project, an amendment to this Permit must be obtained from the Department of Environment and Climate Change under Section 49 of the *Water Resources Act*.

(for) MINISTER

GOVERNMENT OF NEWFOUNDLAND AND LABRADOR

Department of Environment and Climate Change

File No: <u>**526**</u>

Permit No: ALT12996-2023

APPENDIX A

Terms and Conditions for Permit

Water Intake

- 1. The constructed works must be inspected regularly so that action can be taken to undertake repairs as required.
- 2. A temporary water intake system may be placed in an unnamed waterbody to provide water supply for the Concrete Batch Plant in the Valentine Gold Project.
- 3. Pipe zone cutoff walls or other means must be installed to prevent lowering of the water table due to groundwater flow through the porous pipe zone material.
- 4. Where pumping is used to bypass flow, cofferdams must be installed both above and below areas of construction. The Permit Holder must provide pumps with sufficient capacity to prevent washout of cofferdams.
- 5. Cofferdams must be properly designed and constructed of suitable materials to prevent leakage and to resist loss of any material as a result of erosion. Cofferdams must be removed upon completion of their intended function. All material must be removed carefully to prevent disturbance of the water body and to prevent water quality degradation.
- 6. The installation of the water supply pipe must comply with the manufacturers specifications, particularly with regard to pipe zone bedding material, degree of compaction, and maximum minimum pipe cover for design loadings.
- 7. The intake must be fitted with a removable mesh screen or a trash rack.
- 8. Intake ports must be located above the bottom of the stream, lake, or impoundment, but at sufficient depth to be kept submerged at low water levels and below ice level. The intake structure must not draw air.
- 9. Adequate protection must be provided against clogging by sediment, debris, ice, frazil ice, wind, floatation and wave pressure.

General Alterations

- 10. Any work that must be performed below the high water mark must be carried out during a period of low water levels.
- 11. Any flowing or standing water must be diverted around work sites so that work is carried out in the dry.
- 12. Water pumped from excavations or work areas, or any runoff or effluent directed out of work sites, must have silt and turbidity removed by settling ponds, filtration, or other suitable treatment before discharging to a body of water. Effluent discharged into receiving waters must comply with the *Environmental Control Water and Sewage Regulations*, 2003.
- 13. All operations must be carried out in a manner that prevents damage to land, vegetation, and watercourses, and which prevents pollution of bodies of water.

- 14. The use of heavy equipment in streams or bodies of water is not permitted. The operation of heavy equipment must be confined to dry stable areas.
- 15. All vehicles and equipment must be clean and in good repair, free of mud and oil, or other harmful substances that could impair water quality.
- 16. During the construction of concrete components, formwork must be properly constructed to prevent any fresh concrete from entering a body of water. Dumping of concrete or washing of tools and equipment in any body of water is prohibited.
- 17. Wood preservatives such as penta, CCA or other such chemicals must not be applied to timber near a body of water. All treated wood or timber must be thoroughly dry before being brought to any work site and installed.
- 18. Any areas adversely affected by this project must be restored to a state that resembles local natural conditions. Further remedial measures to mitigate environmental impacts on water resources can and will be specified, if considered necessary in the opinion of this Department.
- 19. The bed, banks and floodplains of watercourses, or other vulnerable areas affected by this project, must be adequately protected from erosion by seeding, sodding or placing of rip-rap.
- 20. All waste materials resulting from this project must be disposed of at a site approved by the Department of Digital Government and Service NL.
- 21. Periodic maintenance such as painting, resurfacing, clearing of debris, or minor repairs, must be carried out without causing any physical disruption of any watercourse. Care must be taken to prevent spillage of pollutants into the water.
- 22. The owners of structures are responsible for any environmental damage resulting from dislodgement caused by wind, wave, ice action, or structural failure.
- 23. Sediment and erosion control measures must be installed before starting work. All control measures must be inspected regularly and any necessary repairs made if damage is discovered.
- 24. Fill material must be of good quality, free of fines or other substances including metals, organics, or chemicals that may be harmful to the receiving waters.
- 25. The attached Completion Report (Appendix C) for Permit No. 12996 must be completed and returned to this Department upon completion of the approved works. Pictures must be submitted along with the completion report, showing the project site prior to and after development.
- 26. This Permit is valid for two years from the date of issue. Work must be completed by that date or the application and approval procedure must be repeated.
- 27. The location of the work is highlighted on the Location Map for this Permit attached as Appendix D.
- 28. All work must be carried out within the Permit Holder's legal property boundaries.

Special Conditions

29. The temporary water intake system must be decommissioned after the end of its intended use and restored the site to its original state.

GOVERNMENT OF NEWFOUNDLAND AND LABRADOR

Department of Environment and Climate Change

File No: <u>**526**</u>

Permit No: ALT12996-2023

APPENDIX B

Special Terms and Conditions for Permit

- 1. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall keep all systems and works in good condition and repair and in accordance with all laws, by-laws, directions, rules and regulations of any governmental authority. The Permit Holder or its agent(s), subcontractor(s), or consultant(s) shall immediately notify the Minister if any problem arises which may threaten the structural stability of the systems and works, endanger public safety and/or the environment or adversely affect others and/or any body of water either in or outside the said Project areas. The Permit Holder and its agent(s), subcontractor (s), and consultant(s) shall be responsible for all damages suffered by the Minister and Government resulting from any defect in the systems and works, operational deficiencies/inadequacies, or structural failure.
- 2. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall operate the said Project and its systems and works in a manner which does not cause any water related and/or environmental problems, including but not limited to problems of erosion, deposition, flooding, and deterioration of water quality and groundwater depletion, in or outside the said Project areas. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall be responsible for any and all damages associated with these problems caused as a result of changes, deficiencies, and inadequacies in the operational procedures by the Permit Holder or its agent(s), subcontractor(s), or consultant(s).
- 3. If the Permit Holder or its agent(s), subcontractor(s), or consultant(s) fails to perform, fulfil, or observe any of the terms and conditions, or provisions of this Permit, as determined by this Department, the Minister may, without notice, amend, modify, suspend or cancel this Permit in accordance with the *Water Resources Act*.
- 4. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) indemnify and hold the Minister and Government harmless against any and all liabilities, losses, claims, demands, damages or expenses including legal expenses of any nature whatsoever whether arising in tort, contract, statute, trust or otherwise resulting directly or indirectly from granting this Permit, systems and works in or outside the said Project areas, or any act or omission of the Permit Holder or its agent(s), subcontractor(s), or consultant(s) in or outside the said Project areas, or arising out of a breach or non-performance of any of the terms and conditions, or provisions of this Permit by the Permit Holder or its agent(s), subcontractor(s), or consultant(s).
- 5. This Permit is subject to all provisions of the *Water Resources Act* and any regulations in effect either at the date of this Permit or hereafter made pursuant thereto or any other relevant legislation enacted by the Province of Newfoundland and Labrador in the future.
- 6. This Permit shall be construed and interpreted in accordance with the laws of the Province of Newfoundland and Labrador.

File No: <u>**526**</u>

Permit No: <u>ALT12996-2023</u>

cc: Jeremy Keeping (Western)
Land Management Specialist
Crown Lands Administration
Department of Fisheries, Forestry and Agriculture
jeremykeeping@gov.nl.ca

cc: Western Regional Lands Office Crown Lands Fisheries and Lands Resources WesternRegionLands@gov.nl.ca

cc: Ms. Paula Dawe, P.Eng.
Manager, Water Rights, Investigations and Modelling Section
Water Resources Management Division
Department of Environment and Climate Change
P.O. Box 8700
4th Floor, West Block, Confederation Building
St. John's, NL A1B 4J6
pauladawe@gov.nl.ca

cc: Fisheries Protection Division
Ecosystem Management Branch
Fisheries and Oceans Canada
P.O. Box 5667
St. John's, NL A1C 5X1
FPP-NL@dfo-mpo.gc.ca



Government of Newfoundland and Labrador Department of Environment and Climate Change Water Resources Management Division

Appendix C - Completion Report

	Appendix C - Co	inpletion Report
Pursuant to the Water Resources Act, SNL 2002 cW-4.01, specifically Section(s) 48		
Date:	MARCH 24, 2023	File No: <u>526</u> Permit No: <u>ALT12996-2023</u>
Permit Holder:	Marathon Gold Corporation	
	7 Queensway	
	Grand Falls-Windsor	
	NL A2B 1K9	
	sfinlay@marathon-gold.com	
Attention:	Scott Finlay	
Re:	Valentine Gold Project (unnamed waterbody) - Installation of temporary water intake system for concrete batch plant	
delivery pipe) i	in an unnamed waterbody for supplying v eference to the application dated Februar	water intake system (pump and 76.2 mm HDPE water to concrete batch plant in Valentine Gold cy 23, 2023 and additional information received on
certify the specifical	hat the project described above was comple ations submitted to the Department of Envi	ized to represent the Permit Holder) do hereby ted in accordance with the plans and ronment and Climate Change and that the work and conditions of the Permit issued for this

This completion report must be completed and forwarded to the following address upon completion of the approved work.

Department of Environment and Climate Change Water Resources Management Division PO Box 8700 St. John's NL A1B 4J6

Date:

GOVERNMENT OF NEWFOUNDLAND AND LABRADOR Department of Environment and Climate Change

File No: <u>**526**</u>

Permit No: <u>ALT12996-2023</u>

APPENDIX D Location Map for Permit

Installation of pump and water intake pipeline for concrete batch plant

