

## PERMIT TO CONSTRUCT

---

Pursuant to the *Water Resources Act*, SNL 2002 cW-4.01, specifically Section(s) 37

Date: **APRIL 10, 2023**

File No: **844.352.001**  
Permit No: **WS13000-2023**

Permit Holder: **Town of Trinity Bay North**  
**P.O. Box 91**  
**Port Union, NL**  
**A0C 2J0**  
**townmanager@personainternet.com**


Attention: **Mr. Darryl Johnson, Town Manager**

Re: **Trinity Bay North - Water System Improvements**

---

Permission is hereby given for : **the replacement and installation of two raw water pumps and controls, soda ash chemical feed pumps and controls, pH/chlorine residual analyzer in the pump house; chlorine gas feed system, weigh scales, gas detectors and ejectors, two submersible chlorine booster pumps and a traveling screen pump in the screen house and all related appurtenances as described in a specification and drawings titled, "Municipality of Trinity Bay North Water System Improvements" as received from Meridian Engineering Inc. on January 26, 2023; 17-GI-22-00048.**

- This Permit does not release the Permit Holder from the obligation to obtain appropriate approvals from other concerned municipal, provincial and federal agencies.
- The Permit Holder must obtain the approval of the Crown Lands Administration Division if the project is being carried out on Crown Land.
- This Permit is subject to the terms and conditions indicated in Appendices A and B (attached).
- It should be noted that prior to any significant changes in the design or installation of the proposed works, or in event of changes in ownership or management of the project, an amendment to this Permit must be obtained from the Department of Environment and Climate Change under Section 49 of the *Water Resources Act*.



(for) MINISTER

**APPENDIX A**  
**Terms and Conditions for Permit**

---

**Water & Sewer General**

1. Water pumped from excavations or work areas, or any runoff or effluent directed out of work sites, must have silt and turbidity removed by settling ponds, filtration, or other suitable treatment before discharging to a body of water. Effluent discharged into receiving waters must comply with the *Environmental Control Water and Sewage Regulations, 2003*.
2. All operations must be carried out in a manner that prevents damage to land, vegetation, and watercourses, and which prevents pollution of bodies of water.
3. Any areas adversely affected by this project must be restored to a state that resembles local natural conditions. Further remedial measures to mitigate environmental impacts on water resources can and will be specified, if considered necessary in the opinion of this Department.
4. All waste materials resulting from this project must be disposed of at a site approved by the Department of Digital Government and Service NL.
5. The works proposed must satisfy the requirements of the latest applicable codes and standards, and be consistent with or otherwise address the design criteria set out in this Department's publication *Guidelines for the Design, Construction, and Operation of Water and Sewerage Systems, 2005*, and as amended from time to time.
6. The work must be undertaken in strict compliance with the submitted documents and the latest version of the *Municipal Water, Sewer and Roads Master Construction Specifications*. A copy of all documents, including the *Municipal Water, Sewer and Roads Master Construction Specifications* must be available for viewing at the construction site office at all times.
7. Liaison is to be maintained with the Environmental Scientist representing the Drinking Water and Wastewater Section of this Department, during the construction and operation of the project. They shall be notified of the pre-construction and post-construction meetings so that they may attend, if deemed necessary. They can be reached at telephone (709) 729-2558.
8. Officials of this Department may visit the project from time to time to ensure that work is carried out within the provisions of this Permit, and is not creating any environmental hazard.
9. Any changes in the approved works, or works other than those specified in the application, must be submitted, in writing, to this Department, and approved, in the form of an Amendment to this Permit, prior to any work.
10. Copies of this Permit, as well as any subsequent Amendments, must be provided to the contractor(s) who will be carrying out these works, and to the engineer's site representative.
11. The attached Completion Report (Appendix C) for Permit No. 13000 must be completed and returned to this Department upon completion of the approved works. Pictures must be submitted along with the completion report, showing the project site prior to and after development.
12. This Permit is valid for two years from the date of issue. Work must be completed by that date or the application and approval procedure must be repeated.
13. The drinking water and wastewater system shall be operated and maintained in accordance with the Permit to Operate issued by this Department.

14. Management of stormwater is the responsibility of the municipality or LSD. Stormwater management should focus on ensuring that the post-development stormwater runoff rate will be equal to or less than the pre-development runoff rate. Any stormwater runoff has the potential to contribute to flooding downstream which may have liability issues for the municipality or LSD if not managed properly.
15. The Owner must update any drawings maintained of the drinking water or wastewater system to reflect the modification or replacement of the works, where applicable.

### **Chlorination**

16. The upgrading of the existing chlorination facility must be carried out in such a way as there will be minimal interruption of the water supply and chlorination system. In this regard, water consumers and the Regional Office of the Department of Digital Government and Service NL shall be kept informed and appropriate action taken to address any potential or encountered problems.
17. The door of the chlorination room must open outward, and must be equipped with approved panic hardware. This door shall have mounted on its exterior, a sign **warning** of the presence of chlorine gas.
18. The chlorination room/building/storage area must be equipped with a chlorine leak detection device. The device shall control an audible alarm, and an alarm light located above the entrance door to the chlorine room.
19. Self-contained breathing apparatus or respiratory air-pac protection equipment shall be provided. The equipment shall be stored in convenient locations, but not inside any room where chlorine is used or stored. The unit shall use compressed air, have at least 30 minute capacity, and be compatible with the units used by the regional fire department.
20. The breathing apparatus must be wall mounted in a convenient location in the pump/screen room. The Town of Trinity Bay North shall ensure that the air cylinder is purged and refilled on a regular basis to ensure its safe operation, and shall ensure that the operator(s) is trained in the use of the breathing apparatus.
21. A Chlorine Institute 'Kit A' should be provided in order that emergency leak repairs may be made to the chlorine cylinders when necessary. The Kit should be stored near the emergency breathing apparatus, and not in the same room as the chlorine cylinders.
22. The vacuum regulator vents must be vented to a safe location where personnel will not be endangered from the escaping gas. They shall not under any circumstance be vented in the vicinity of an exit door or through an unheated space (ie. attic).
23. The injector for the chlorination system shall be located as close as possible to the diffuser (preferably attached) in order to minimize the pressurized chlorine solution line. The chlorine injection lance shall be installed in the pipe so that the chlorine solution is being injected within the flow of water to ensure appropriate mixing.
24. A sample tap shall be provided so that water samples can be obtained from the raw water source and from an appropriate location after chlorination. Taps used shall be of the smooth-nosed type without interior or exterior threads and shall not have a screen, aerator or other such appurtenance.
25. An emergency shower and eye wash station that is in compliance with ANSI Z358.1-2014 and meets the requirements of the appropriate Safety Data Sheet (SDS) shall be installed in a convenient location(s) within each facility.
26. The emergency eye wash stations shall be located within 4.5 m of both the chlorine equipment room or chlorine storage room exit doors. An emergency eye wash shall also be installed in the polymer room. All eye wash stations not connected to the potable water system must be capable of providing a continuous 15 minute flush as a minimum, using potable water or equivalent.
27. The chlorinator and chlorine vacuum lines shall not be located on an outside wall to prevent exposure to low temperatures.

## **Water Treatment**

28. There shall be adequate storage handling facilities for 30 days of dry chemical supply.
29. All drains and vents shall be equipped with screens to prevent the entry of insects, birds and rodents.
30. The ends of drains and overflows shall be located so as to prevent erosion. Where necessary, concrete or similar splash plates shall be located below the end of the overflow, and the immediate surrounding area shall be filled to a depth of 10 cm with 19 mm minus stone to prevent ponding.
31. A backflow prevention device, in this case a hose connection vacuum breaker, non removable, meeting or exceeding CSA 64.2, shall be attached to any hose bibb connection, to prevent the possibility of contaminants entering the potable water distribution system due to back-siphonage.
32. Chemical mixing tanks shall be located as near as possible to the point of application to minimize the length of feed lines.
33. All components, lubricants and chemicals provided shall be compatible for use with drinking water and shall meet the requirements of ANSI/NSF 60 Drinking Water Treatment Chemical Standard and ANSI/NSF 61 Drinking Water and System Component Standard and any other standard applicable to potable water.
34. The owner shall ensure that all chemicals used in the treatment process and all materials contacting the water are of Food Grade quality and meet both the American Water Works Association (AWWA) quality criteria as set out in AWWA standards and the American National Standards Institute (ANSI) and the National Sanitation Foundation (NSF) safety criteria as set out in ANSI/NSF 60 or ANSI/NSF 61 standards and any other applicable standards.
35. Appropriate backflow prevention devices meeting or exceeding the CSA 64 Standard shall be installed on all potable water lines where a cross connection may exist or be created, to prevent the possibility of contaminants entering the potable water distribution system due to back-siphonage or back-pressure.
36. Continuous on-line monitoring of pH and chlorine is required.

## **SCADA- PtC**

37. The SCADA system shall not be on the same network as other business or municipal computing systems.
38. The SCADA system shall not be located below the level of any water storage basin used in the treatment process or any large diameter pipes.
39. SCADA systems which have network connectivity must have anti-virus applications installed.
40. The computer/master terminal unit containing the SCADA system master database and interface must be kept in a separate server room that can be locked.
41. Multiple firewalls must be installed on the SCADA system if remote access/login is allowed.
42. A spare computer must be provided that contains a backup copy of the SCADA system master database and interface.

**APPENDIX B**

**Special Terms and Conditions for Permit**

---

1. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall keep all systems and works in good condition and repair and in accordance with all laws, by-laws, directions, rules and regulations of any governmental authority. The Permit Holder or its agent(s), subcontractor(s), or consultant(s) shall immediately notify the Minister if any problem arises which may threaten the structural stability of the systems and works, endanger public safety and/or the environment or adversely affect others and/or any body of water either in or outside the said Project areas. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall be responsible for all damages suffered by the Minister and Government resulting from any defect in the systems and works, operational deficiencies/inadequacies, or structural failure.
2. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall operate the said Project and its systems and works in a manner which does not cause any water related and/or environmental problems, including but not limited to problems of erosion, deposition, flooding, and deterioration of water quality and groundwater depletion, in or outside the said Project areas. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall be responsible for any and all damages associated with these problems caused as a result of changes, deficiencies, and inadequacies in the operational procedures by the Permit Holder or its agent(s), subcontractor(s), or consultant(s).
3. If the Permit Holder or its agent(s), subcontractor(s), or consultant(s) fails to perform, fulfil, or observe any of the terms and conditions, or provisions of this Permit, as determined by this Department, the Minister may, without notice, amend, modify, suspend or cancel this Permit in accordance with the *Water Resources Act*.
4. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) indemnify and hold the Minister and Government harmless against any and all liabilities, losses, claims, demands, damages or expenses including legal expenses of any nature whatsoever whether arising in tort, contract, statute, trust or otherwise resulting directly or indirectly from granting this Permit, systems and works in or outside the said Project areas, or any act or omission of the Permit Holder or its agent(s), subcontractor(s), or consultant(s) in or outside the said Project areas, or arising out of a breach or non-performance of any of the terms and conditions, or provisions of this Permit by the Permit Holder or its agent(s), subcontractor(s), or consultant(s).
5. This Permit is subject to all provisions of the *Water Resources Act* and any regulations in effect either at the date of this Permit or hereafter made pursuant thereto or any other relevant legislation enacted by the Province of Newfoundland and Labrador in the future.
6. This Permit shall be construed and interpreted in accordance with the laws of the Province of Newfoundland and Labrador.

- cc: Mr. Jason Strickland, P. Eng.  
Meridian Engineering Inc.  
10 Thompson Street  
Clarenville, NL A5A 1Y9  
jstrickland@meridianengineering.ca
- cc: Ms. Deneen Spracklin, P.Eng.  
Manager, Drinking Water and Wastewater Section  
Water Resources Management Division  
Department of Environment and Climate Change  
P.O. Box 8700  
4th Floor, West Block, Confederation Building  
St. John's, NL A1B 4J6  
dspracklin@gov.nl.ca
- cc: Mr. Inayat Rehman, P.Eng.  
Regional Engineer  
Department of Transportation and Infrastructure  
P.O. Box 8700  
St. John's, NL A1B 4J6  
inayatrehman@gov.nl.ca
- cc: Mr. Michael Duke (Clarenville - Eastern)  
Manager  
Digital Government and Service NL  
8 Myers Ave  
Clarenville, NL A5A 1T5  
michaelduke@gov.nl.ca



**Appendix C - Completion Report**

Pursuant to the *Water Resources Act*, SNL 2002 cW-4.01, specifically Section(s) 37

Date: **APRIL 10, 2023**

File No: **844.352.001**  
Permit No: **WS13000-2023**

Permit Holder: **Town of Trinity Bay North  
P.O. Box 91  
Port Union, NL  
A0C 2J0  
townmanager@personainternet.com**

Attention: **Mr. Darryl Johnson, Town Manager**

Re: **Trinity Bay North - Water System Improvements**

Permission was given for : **the replacement and installation of two raw water pumps and controls, soda ash chemical feed pumps and controls, pH/chlorine residual analyzer in the pump house; chlorine gas feed system, weigh scales, gas detectors and ejectors, two submersible chlorine booster pumps and a traveling screen pump in the screen house and all related appurtenances as described in a specification and drawings titled, "Municipality of Trinity Bay North Water System Improvements" as received from Meridian Engineering Inc. on January 26, 2023; 17-GI-22-00048.**

*I (the Permit Holder named above or agent authorized to represent the Permit Holder) do hereby certify that the project described above was completed in accordance with the plans and specifications submitted to the Department of Environment and Climate Change and that the work was carried out in strict compliance with the terms and conditions of the Permit issued for this project.*

Date: \_\_\_\_\_ Signature: \_\_\_\_\_

This completion report must be completed and forwarded to the following address upon completion of the approved work.

Department of Environment and Climate Change  
Water Resources Management Division  
PO Box 8700  
St. John's NL A1B 4J6