

# Government of Newfoundland and Labrador Department of Environment and Climate Change Water Resources Management Division

#### PERMIT TO CONSTRUCT

Pursuant to the Water Resources Act, SNL 2002 cW-4.01, specifically Section(s) 37

Date: APRIL 10, 2024 File No: <u>844.133.003</u> Permit No: <u>WS13578-2024</u>

Permit Holder: LSD of Hickman's Harbour-Robinson's Bight

PO Box 64

Hickman's Harbour NLA0C 1P0

lsd-hhrb@hotmail.com

Attention: Ms. Elizabeth Marsh, Chairperson

Re: Hickman's Harbour-Robinson's Bight - Watermain Interconnection

Permission is hereby given for: the installation of approximately 220 m of 100 mm HDPE watermain and related appurtenances as described in the drawings titled, "Local Service District of Hickman's Harbour/Robinson's Bight Watermain Interconnection" as received from Meridian Engineering Inc. on March 18, 2024; 17-GI-24-00002.

- This Permit does not release the Permit Holder from the obligation to obtain appropriate approvals from other concerned municipal, provincial and federal agencies.
- The Permit Holder must obtain the approval of the Crown Lands Administration Division if the project is being carried out on Crown Land.
- This Permit is subject to the terms and conditions indicated in Appendices A and B (attached).
- It should be noted that prior to any significant changes in the design or installation of the proposed works, or in event of changes in ownership or management of the project, an amendment to this Permit must be obtained from the Department of Environment and Climate Change under Section 49 of the *Water Resources Act*.

(for) MINISTER

# GOVERNMENT OF NEWFOUNDLAND AND LABRADOR

Department of Environment and Climate Change

File No: **844.133.003** Permit No: **WS13578-2024** 

#### APPENDIX A

#### **Terms and Conditions for Permit**

#### Water & Sewer General

- 1. Water pumped from excavations or work areas, or any runoff or effluent directed out of work sites, must have silt and turbidity removed by settling ponds, filtration, or other suitable treatment before discharging to a body of water. Effluent discharged into receiving waters must comply with the *Environmental Control Water and Sewage Regulations*, 2003.
- 2. All operations must be carried out in a manner that prevents damage to land, vegetation, and watercourses, and which prevents pollution of bodies of water.
- 3. Any areas adversely affected by this project must be restored to a state that resembles local natural conditions. Further remedial measures to mitigate environmental impacts on water resources can and will be specified, if considered necessary in the opinion of this Department.
- 4. All waste materials resulting from this project must be disposed of at a site approved by the Department of Digital Government and Service NL.
- 5. The works proposed must satisfy the requirements of the latest applicable codes and standards, and be consistent with or otherwise address the design criteria set out in this Department's publication *Guidelines for the Design*, *Construction, and Operation of Water and Sewerage Systems*, 2005, and as amended from time to time.
- 6. The work must be undertaken in strict compliance with the submitted documents and the latest version of the *Municipal Water, Sewer and Roads Master Construction Specifications*. A copy of all documents, including the *Municipal Water, Sewer and Roads Master Construction Specifications* must be available for viewing at the construction site office at all times.
- 7. Liaison is to be maintained with the Environmental Scientist representing the Drinking Water and Wastewater Section of this Department, during the construction and operation of the project. They shall be notified of the preconstruction and post-construction meetings so that they may attend, if deemed necessary. They can be reached at telephone (709)729-2558.
- 8. Officials of this Department may visit the project from time to time to ensure that work is carried out within the provisions of this Permit, and is not creating any environmental hazard.
- 9. Any changes in the approved works, or works other than those specified in the application, must be submitted, in writing, to this Department, and approved, in the form of an Amendment to this Permit, prior to any work.
- 10. Copies of this Permit, as well as any subsequent Amendments, must be provided to the contractor(s) who will be carrying out these works, and to the engineer's site representative.
- 11. The attached Completion Report (Appendix C) for Permit No. 13578 must be completed and returned to this Department upon completion of the approved works. Pictures must be submitted along with the completion report, showing the project site prior to and after development.
- 12. This Permit is valid for two years from the date of issue. Work must be completed by that date or the application and approval procedure must be repeated.

- 13. The drinking water and wastewater system shall be operated and maintained in accordance with the Permit to Operate issued by this Department.
- 14. Management of stormwater is the responsibility of the municipality or LSD. Stormwater management should focus on ensuring that the post-development stormwater runoff rate will be equal to or less than the pre-development runoff rate. Any stormwater runoff has the potential to contribute to flooding downstream which may have liability issues for the municipality or LSD if not managed properly.
- 15. The Owner must update any drawings maintained of the drinking water or wastewater system to reflect the modification or replacement of the works, where applicable.

### **Water Systems**

- 16. Under no circumstances shall sewage be permitted to enter the waterline trench during or after construction.
- 17. All new waterlines and appurtenances shall be hydrostatically tested in accordance with the *Municipal Water, Sewer* and Roads Specifications.
- 18. Water mains must not pass within 15 metres of any part of a sewage disposal system. Water service lines must not pass within 7.5 metres of a sewage disposal system. In general the following conditions should be met in regards to water service lines:
  - (a) There should be no joint in the service line between the building and the connection to the watermain.
  - (b) The groundwater level should not be above the service line.
  - (c) The service line should be located upslope of the sewage disposal system.
  - If the above conditions are not met, consideration should be given to increasing the distance between the service line and the sewage disposal system, providing extra protection against contamination.
- 19. All components, lubricants and chemicals provided shall be compatible for use with drinking water and shall meet the requirements of ANSI/NSF 60 Drinking Water Treatment Chemical Standard and ANSI/NSF 61 Drinking Water and System Component Standard and any other standard applicable to potable water.
- 20. Backflow prevention devices should/must be installed on service connections where there is a high risk of contamination of the potable water supply.
- 21. All new lines and appurtenances must be disinfected by an approved method described in the latest edition of the AWWA C651 Standard for Disinfecting Watermains and using only chlorine products that meet the NSF 60 standard.
- 22. After final flushing and before the new water main is commissioned into service, bacteriological sampling must be conducted as per the latest edition of the AWWA C651 Standard for Disinfecting Watermains. Two acceptable options are available: (1) two consecutive sets of bacteriological samples, taken at least 16 hours apart, must be collected and tested for bacteriological quality, or (2) following a 16 hour rest period two consecutive sets of samples, taken 15 minutes apart, must be collected and tested for bacteriological quality. Sets of samples shall be collected for every 366 m of new water main including the end of the main line and the end of each branch line. These sampling locations shall be determined by the engineer. A copy of test results must be submitted to this Department (Water Resources Management Division) before the new watermain is placed into service. In the event of any bacteria detected in the sample results, flushing and re-sampling may be attempted or the disinfection process will need to be repeated until results for two consecutive sets of samples are bacteria free. Where necessary, this Department should be contacted to determine provisions for the disposal of heavily chlorinated water.
- 23. For the purpose of disinfecting new or upgraded watermains, connection may only be made to the existing watermain provided a valve is installed that maintains a water tight seal. This valve may be operated to flush the new water extension before disinfection and post disinfection provided adequate measures and procedures are followed to avoid a backflow and contamination of the existing system.
- 24. Wherever possible, water distribution system layouts should be designed to eliminate dead-end sections. Where dead-end mains cannot be avoided, they should be provided with a fire hydrant, blow off, or other acceptable measures taken to prevent problems associated with stagnation.

## Miscellaneous

25. The Permit Holder must prevent erosion of drainage ditches, streams or other natural bodies of water by installing rip-rap and/or sodding.

# GOVERNMENT OF NEWFOUNDLAND AND LABRADOR

Department of Environment and Climate Change

File No: <u>844.133.003</u> Permit No: **WS13578-2024** 

#### APPENDIX B

#### **Special Terms and Conditions for Permit**

- 1. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall keep all systems and works in good condition and repair and in accordance with all laws, by-laws, directions, rules and regulations of any governmental authority. The Permit Holder or its agent(s), subcontractor(s), or consultant(s) shall immediately notify the Minister if any problem arises which may threaten the structural stability of the systems and works, endanger public safety and/or the environment or adversely affect others and/or any body of water either in or outside the said Project areas. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall be responsible for all damages suffered by the Minister and Government resulting from any defect in the systems and works, operational deficiencies/inadequacies, or structural failure.
- 2. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall operate the said Project and its systems and works in a manner which does not cause any water related and/or environmental problems, including but not limited to problems of erosion, deposition, flooding, and deterioration of water quality and groundwater depletion, in or outside the said Project areas. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall be responsible for any and all damages associated with these problems caused as a result of changes, deficiencies, and inadequacies in the operational procedures by the Permit Holder or its agent(s), subcontractor(s), or consultant(s).
- 3. If the Permit Holder or its agent(s), subcontractor(s), or consultant(s) fails to perform, fulfil, or observe any of the terms and conditions, or provisions of this Permit, as determined by this Department, the Minister may, without notice, amend, modify, suspend or cancel this Permit in accordance with the *Water Resources Act*.
- 4. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) indemnify and hold the Minister and Government harmless against any and all liabilities, losses, claims, demands, damages or expenses including legal expenses of any nature whatsoever whether arising in tort, contract, statute, trust or otherwise resulting directly or indirectly from granting this Permit, systems and works in or outside the said Project areas, or any act or omission of the Permit Holder or its agent(s), subcontractor(s), or consultant(s) in or outside the said Project areas, or arising out of a breach or non-performance of any of the terms and conditions, or provisions of this Permit by the Permit Holder or its agent(s), subcontractor(s), or consultant(s).
- 5. This Permit is subject to all provisions of the *Water Resources Act* and any regulations in effect either at the date of this Permit or hereafter made pursuant thereto or any other relevant legislation enacted by the Province of Newfoundland and Labrador in the future.
- 6. This Permit shall be construed and interpreted in accordance with the laws of the Province of Newfoundland and Labrador.

File No: **844.133.003** Permit No: **WS13578-2024** 

cc: Stephen Locke, P.Eng.
Meridian Engineering Inc.
10 Thompson Street
Clarenville, NL A5A 1Y9
slocke@meridianengineering.ca

cc: Ms. Deneen Spracklin, P.Eng.
Manager, Drinking Water and Wastewater Section
Water Resources Management Division
Department of Environment and Climate Change
P.O. Box 8700
4th Floor, West Block, Confederation Building
St. John's, NL A1B 4J6
dspracklin@gov.nl.ca

cc: Mr. Inayat Rehman, P.Eng.
Regional Engineer
Department of Transportation and Infrastructure
P.O. Box 8700
St. John's, NL A1B 4J6
inayatrehman@gov.nl.ca

cc: Mr. Michael Duke (Clarenville - Eastern)
Manager
Digital Government and Service NL
8 Myers Ave
Clarenville, NL A5A 1T5
michaelduke@gov.nl.ca



# Government of Newfoundland and Labrador

## **Department of Environment and Climate Change Water Resources Management Division**

## **Appendix C - Completion Report**

e:	APRIL 10, 2024	File No: <u>844.133.003</u> Permit No: <u>WS13578-2024</u>
rmit Holder:	LSD of Hickman's Harbour-Robinson's Bight PO Box 64	
	Hickman's Harbour NL A0C 1P0 lsd-hhrb@hotmail.com	
	isa iiii s/w/iiotiiiaii.com	
ention:	Ms. Elizabeth Marsh, Chairperson	
	Hickman's Harbour-Robinson's Bight - Watermain Interconnection	
urtenances a	given for : the installation of approximately 220 m of 100 mm HDP as described in the drawings titled, "Local Service District of Hick	E watermain and related man's Harbour/Robinson's Bigl
I (the Per the proje	given for: the installation of approximately 220 m of 100 mm HDP as described in the drawings titled, "Local Service District of Hick erconnection" as received from Meridian Engineering Inc. on Marcermit Holder named above or agent authorized to represent the Permit ect described above was completed in accordance with the plans and stant of Environment and Climate Change and that the work was carr	E watermain and related man's Harbour/Robinson's Biglich 18, 2024; 17-GI-24-00002.  It Holder) do hereby certify that specifications submitted to the
I (the Per the proje	given for: the installation of approximately 220 m of 100 mm HDP as described in the drawings titled, "Local Service District of Hick erconnection" as received from Meridian Engineering Inc. on Marconnection as received from Meridian Engineering Inc. on Marcornection as received from Meridian Engineering Inc. on Meridian Engineering Inc. on Meridian Engineering In	E watermain and related man's Harbour/Robinson's Biglich 18, 2024; 17-GI-24-00002.  It Holder) do hereby certify that specifications submitted to the

Department of Environment and Climate Change Water Resources Management Division PO Box 8700 St. John's NL A1B 4J6