



Government of Newfoundland and Labrador  
Department of Municipal Affairs and Environment  
Water Resources Management Division

---

Pursuant to the *Water Resources Act*, SNL 2002 cW-4.01, specifically Section(s)

Date: **DECEMBER 14, 2017**

File No: **NDOM17-038**  
Permit No: **GW9502-2017**

Permit Holder: **Marine Harvest Atlantic Canada  
124-1334 Island Highway  
Campbell River, BC  
V9W 8H9**


Attention: **Dean Guest**

Re: **Marine Harvest Atlantic Canada Test Wells c/o FracFlow Consultants Inc.**

---

Permission is hereby given for :

- This Permit does not release the Permit Holder from the obligation to obtain appropriate approvals from other concerned municipal, provincial and federal agencies.
- This Permit is subject to the terms and conditions indicated in Appendices A and B (attached).
- It should be noted that prior to any significant changes in the design or installation of the proposed works, or in event of changes in ownership or management of the project, an amendment to this Permit must be obtained from the Department of Municipal Affairs and Environment under Section 49 of the *Water Resources Act*.
- Failure to comply with the terms and conditions will render this Permit null and void, place the Permit Holder and their agent(s) in violation of the *Water Resources Act* and make the Permit Holder responsible for taking any remedial measures as may be prescribed by this Department.

  
MINISTER

**APPENDIX A**  
**Terms and Conditions for Permit**

---

**Non-domestic (GPS Coordinates)**

1. The well and/or borehole must be constructed at or near the given coordinate as provided in the non-domestic well application: N 48.5475, W 58.519902778. Any additional information on well or borehole locations can be acquired by contacting the groundwater environmental scientist at (709) 729-1671 or GroundwaterSection@gov.nl.ca.

**Non-Domestic (Construction)**

2. Water disinfected by a National Sanitation Foundation (NSF) certified chlorine product must be used for the drilling and clean up operations.
3. Construction of each well must include carbon steel casing to a minimum depth that extends 6 meters into the bedrock and impedes flow of potentially contaminated surface water and/or shallow groundwater to the well. A drive shoe must be used to set the casing into the bedrock.
4. Casing joins must be of continuous weld.
5. The well annulus must be a minimum of 50 millimetres (2 inches) from the outside of the casing to the wall of the borehole and sealed with appropriate grout and/or cement from the bottom of the well casing/drive shoe to the ground surface. If a 150 millimetre (6 inch) casing is used, then a minimum of a 250 millimetre (10 inch) borehole is required.
6. In the course of drilling the well and during the development stage, if salty, sulphurous, or other water that might impair the quality of potable water is encountered, the well driller must seal off that water by a method approved by the Minister.
7. The well driller must take all other reasonable measures necessary to ensure that contaminated surface water, shallow groundwater, and/or other water that might impair the quality of potable water will not enter the well.
8. Water well construction data must include the precise location of the newly completed well taken in latitude/longitude format.

**Non-Domestic (General)**

9. The well must be drilled and completed by a water well driller licenced by the Government of Newfoundland and Labrador, and constructed according to the Water Resources Act and the Well Drilling Regulations under that Act.
10. A Completion Report must be provided to this department within 30 days after well construction is complete.
11. Water well construction data including Drilled Water Well Record(s) and pumping test results for the well must be attached to the Completion Report.
12. This permit is valid for one (1) year from the date of issuance.
13. The well owner is responsible for compliance with this permit.
14. Pesticides, herbicides and fertilizers must not be used within a 100 metre radius of the wellhead.

**Non-Domestic-Finished Wellhead**

15. The area immediately surrounding the well must be sloped away from the well and grass covered to a minimum distance of 5 metres in all directions.

---

16. The wellhead must be completed to a minimum height of 0.6 metres above finished grade.
17. The wellhead must be completed with a double vented (screened) metal vermin-proof well cap with electrical access through the well cap.
18. Water supply from the well must utilize a pitless adaptor installed below the frost line.
19. There must be no holes, slots, or other openings made in the well casing except for the installation of a properly sealed pitless adapter.
20. If an electrical ground wire or other such attachment to the well casing is necessary, it must be attached to a steel anchor that has been welded to the outside of the well casing.
21. If a well pump is to be suspended, it must be done utilizing a stainless steel cable attached to an industry approved well hanger inside the wellhead.
22. The well casing and finished wellhead must be sealed (water tight) except for the screened vent.

#### **Non-Domestic (Development)**

23. Well development discharge water must be monitored continually for salinity due to the sites close proximity to the ocean.

#### **Non-Domestic (Pumping Test)**

24. During the pumping test, discharge water must be monitored continually for salinity.

---

25. Any existing wells in the vicinity of the new wellhead must be monitored during the pumping test. Any changes in water level must be recorded, analyzed, and reported with the completion report.
26. A 72 hour aquifer pumping test is required for the well in accordance with the Water Resources Management Division document Guidelines for Aquifer Pumping Tests. A final report, written by a hydrogeologist or qualified person and providing the information as stated in the guidelines, including chemical analyses of the water, must be forwarded to this department. This report must be submitted with the completion report.
27. An air lift test is required for a minimum of 60 minutes which will include a water sample at the end for inorganic analysis as per attached parameter list.
28. Prior to commencing a long-term aquifer test, a step drawdown test must be conducted to estimate the rate that can be maintained by the well for extended periods of time. The step drawdown test should consist of at least 4 steps and each step should be of at least 30 minutes duration. The pumping rates that are used for this test are determined from the driller's estimate of the well yield. If four steps are used, the first should be conducted at a rate of about one-quarter of the well yield estimate provided by the driller. This rate is maintained for 30 to 60 minutes and then the next step is begun without stopping for recovery. Each successive step should be run at a rate that is approximately double the rate of the step prior. The step drawdown test must be evaluated by a qualified professional prior to the constant rate pumping test to evaluate a sustainable pumping rate.

#### **Non-Domestic (Water Quality)**

29. A minimum of two water samples must be collected from the well at the wellhead during the aquifer pumping test utilizing proper sampling protocol. The first water sample must be collected not less than 30 minutes or more than two hours into the pumping period, and the second or last water sample must be collected during the last hour of the pumping period. Water samples must be submitted to an accredited water analysis laboratory for testing as per the attached parameter list. As a part of the completion report, a copy of the analytical results must be sent to this department.

30. A take-off valve is required in the discharge from the well, located before chlorination and/or treatment is applied, for the purpose on water quality monitoring.

---

31. A permanent sampling port is also recommended in the discharge from chlorination or other treatment device for the purpose of measuring effectiveness of treatment.
32. Two Total Petroleum Hydrocarbons (TPH) screening samples are required during the aquifer pumping test. The first TPH sample set must be taken just after the first inorganic sample is taken during the first two hours of the pumping test and the second TPH sample must be taken just after the second inorganic sample during the last two hours of the aquifer pumping test. The results of both TPH samples must accompany the inorganic sample results as a part of the well completion report.

**Water Use Licence Requirement**

33. The Permit Holder must obtain a water use licence under the Water Resources Act (Contact: Dr. Amir Ali Khan at 709-729-2295). The application (pages 1 and 2 only) and fee schedule are available at the following links:  
[http://www.mae.gov.nl.ca/waterres/regulations/appforms/application\\_for\\_wul.pdf](http://www.mae.gov.nl.ca/waterres/regulations/appforms/application_for_wul.pdf) and [http://www.mae.gov.nl.ca/waterres/regulations/appforms/fee\\_schedule\\_app\\_wul.pdf](http://www.mae.gov.nl.ca/waterres/regulations/appforms/fee_schedule_app_wul.pdf)

GOVERNMENT OF NEWFOUNDLAND AND LABRADOR  
Department of Municipal Affairs and Environment

File No: NDOM17-038  
Permit No: GW9502-2017

**APPENDIX B**  
**Special Terms and Conditions for Permit**

---

1. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall keep all systems and works in good condition and repair and in accordance with all laws, by-laws, directions, rules and regulations of any governmental authority. The Permit Holder or its agent(s), subcontractor(s), or consultant(s) shall immediately notify the Minister if any problem arises which may threaten the structural stability of the systems and works, endanger public safety and/or the environment or adversely affect others and/or any body of water either in or outside the said Project areas. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall be responsible for all damages suffered by the Minister and Government resulting from any defect in the systems and works, operational deficiencies/inadequacies, or structural failure.
  2. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall operate the said Project and its systems and works in a manner which does not cause any water related and/or environmental problems, including but not limited to problems of erosion, deposition, flooding, and deterioration of water quality and groundwater depletion, in or outside the said Project areas. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall be responsible for any and all damages associated with these problems caused as a result of changes, deficiencies, and inadequacies in the operational procedures by the Permit Holder or its agent(s), subcontractor(s), or consultant(s).
  3. If the Permit Holder or its agent(s), subcontractor(s), or consultant(s) fails to perform, fulfil, or observe any of the terms and conditions, or provisions of this Permit and/or Ministerial orders and guidelines, as determined by this Department, the Minister may, after providing ten (10) day notice to the Permit Holder, amend, modify, suspend or cancel this Permit in accordance with the *Water Resources Act*.
  4. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) indemnify and hold the Minister and Government harmless against any and all liabilities, losses, claims, demands, damages or expenses including legal expenses of any nature whatsoever whether arising in tort, contract, statute, trust or otherwise resulting directly or indirectly from granting this Permit, systems and works in or outside the said Project areas, or any act or omission of the Permit Holder or its agent(s), subcontractor(s), or consultant(s) in or outside the said Project areas, or arising out of a breach or non-performance of any of the terms and conditions, or provisions of this Permit by the Permit Holder or its agent(s), subcontractor(s), or consultant(s).
  5. This Permit is subject to all provisions of the *Water Resources Act* and any regulations in effect either at the date of this Permit or hereafter made pursuant thereto or any other relevant legislation enacted by the Province of Newfoundland and Labrador in the future.
  6. This Permit shall be construed and interpreted in accordance with the laws of the Province of Newfoundland and Labrador.
-

cc: Amir Ali Khan, Ph.D., P.Eng.  
Manager, Water Rights, Investigations and Modelling Section  
Water Resources Management Division  
Department of Municipal Affairs and Environment  
P.O. Box 8700  
4th Floor, West Block, Confederation Building  
St. John's, NL A1B 4J6  
akhan@gov.nl.ca

cc: Groundwater Section File Copy

cc: Town of Stephenville  
Ms. Carolyn Lidstone  
P.O. Box 420  
Stephenville, NL A2N 2Z5  
manager@town.stephenville.nf.ca



Government of Newfoundland and Labrador  
Department of Municipal Affairs and Environment  
Water Resources Management Division

### Appendix C - Completion Report

Pursuant to the *Water Resources Act*, SNL 2002 cW-4.01, specifically Section(s)

Date: **DECEMBER 14, 2017**

File No: **NDOM17-038**  
Permit No: **GW9502-2017**

Permit Holder: **Marine Harvest Atlantic Canada  
124-1334 Island Highway  
Campbell River, BC  
V9W 8H9**

Attention: **Dean Guest**

Re: **Marine Harvest Atlantic Canada Test Wells c/o FracFlow Consultants Inc.**

Permission was given for :

*I (the Permit Holder named above or agent authorized to represent the Permit Holder) do hereby certify that the project described above was completed in accordance with the plans and specifications submitted to the Department of Municipal Affairs and Environment and that the work was carried out in strict compliance with the terms and conditions of the Permit issued for this project.*

Date: \_\_\_\_\_ Signature: \_\_\_\_\_

This completion report must be completed and forwarded to the following address upon completion of the approved work.

Department of Municipal Affairs and Environment  
Water Resources Management Division  
PO Box 8700  
St. John's NL, A1B 4J6