

Real Time Water Quality Report Southwest Brook below Southwest Pond

Deployment Period 2012-10-10 to 2012-12-08

2012-12-12



Government of Newfoundland & Labrador
Department of Environment and
Conservation
Water Resources Management Division

General

- This station is operated cooperatively with the Miawpukek First Nation (Conne River) as a Pilot Project for Drinking Water Source Monitoring. This is the only known application of Real Time Water Quality Monitoring for a drinking water source for any First Nations community in Canada.
- The Water Resources Management Division (WRMD) staff monitors the real-time web page on a daily basis. Any unusual observations are investigated, with site visits being carried out as warranted.
- Operators at Conne River are informed of any significant water quality events or instrumentation problems by WRMD.
- Site visits for QA/QC purposes are conducted by WRMD approximately four times per year.
- Monthly calibration and maintenance is undertaken by Cyrus Lambert at the Conne River Water Treatment Plant.

Maintenance and Calibration of Instrumentation

- The regular **DataSonde**® (s/n 44422) was cleaned and freshly calibrated and installed on October 10, 2012 and remained deployed continuously until December 8, a 58 day period.
- The regular QA/QC **MiniSonde**® (s/n 44998) was cleaned and freshly calibrated and used during the deployment and removal for QA/QC measurements.

Quality Assurance / Quality Control (QA/QC) Measures

• As part of the QA/QC protocol, an assessment of the reliability of data recorded by an instrument is made at the beginning and end of the deployment period. The procedure is based on the approach used by the United States Geological Survey. See **Table 1**.

	Rank				
Parameter	Excellent	Good	Fair	Marginal	Poor
Temperature (oC)	<=+/-0.2	>+/-0.2 to 0.5	>+/-0.5 to 0.8	>+/-0.8 to 1	<+/-1
pH (unit)	<=+/-0.2	>+/-0.2 to 0.5	>+/-0.5 to 0.8	>+/-0.8 to 1	>+/-1
Sp. Conductance (µS/cm)	<=+/-3	>+/-3 to 10	>+/-10 to 15	>+/-15 to 20	>+/-20
Sp. Conductance $> 35 \mu \text{S/cm}$ (%)	<=+/-3	>+/-3 to 10	>+/-10 to 15	>+/-15 to 20	>+/-20
Dissolved Oxygen (mg/L)	<=+/-0.3	>+/-0.3 to 0.5	>+/-0.5 to 0.8	>+/-0.8 to 1	>+/-1
Turbidity <40 NTU (NTU)	<=+/-2	>+/-2 to 5	>+/-5 to 8	>+/-8 to 10	>+/-10
Turbidity > 40 NTU (%)	<=+/-5	>+/-5 to 10	>+/-10 to 15	>+/-15 to 20	>+/-20

Table 1

• Upon deployment and removal, a QA/QC MiniSonde® is temporarily deployed along side the Field DataSonde®. Values for each recorded parameter are compared between the two instruments. Based on the difference between parameters recorded by the Field DataSonde® and QA/QC MiniSonde® a qualitative statement (Ranking) is usually made on the data.

- The ranking at the beginning and end of the deployment period are shown in **Table 2**.
- Both pH and Dissolved Oxygen ranked 'Fair" upon removal; having a difference of 0.61 (pH units) and 0.61 mg/L respectively. Variations in this range are not uncommon for a deployment period lasting nearly 2 months.
- With the exception of water quantity data (Stage and Flow), all data used in the preparation of the graphs and subsequent discussion below adhere to this stringent QA/QC protocol. Water Survey of Canada is responsible for QA/QC of water quantity data. Corrected data can be obtained upon request.

Southwest Brook below Southwest Pond (NF02ZE0033)				
Date (yyyy-mm-dd)	Parameter	Ranking		
2012-10-10 Deployment	Temp (°C)	Excellent		
	pH (units)	Excellent		
	Sp. Conductivity (uS/cm)	Excellent		
	Dissolved Oxygen (mg/L)	Excellent		
	Turbidity (NTU)	Excellent		
2012-12-08 Removal	Temp (°C)	Excellent		
	pH (units)	Fair		
	Sp. Conductivity (uS/cm)	Excellent		
	Dissolved Oxygen (mg/L)	Fair		
	Turbidity (NTU)	Excellent		

Table 2

Data Interpretation

- The water temperature (**Figure 1**) ranged from a minimum of -0.20 °C to a maximum of 13.82 °C, with temperature decreasing over the deployment period.
- There sometimes appears to be a correlation with stage, as there is sometimes a temporary increase in water temperature during the rising leg of the hydrograph.
- There is less diurnal variation when stage is increased.




Figure 1

- Throughout the deployment period pH values (**Figure 2**) ranged from a minimum of 5.09 to a maximum of 5.91 with all the values falling well below the recommended range (6.5 9.0) for the CCME *Canadian Water Quality Guidelines for the Protection of Aquatic Life*.
- There was very little variation in pH over this deployment period.
- The background pH of this stream is normally lower than the lower limit of the recommended range.




Figure 2

- The specific conductivity (**Figure 3**) ranged from a minimum of 19.0 μS/cm to a maximum of 21.7 μS/cm over the deployment period.
- During this deployment period, there was very little change in specific conductivity.
- A direct relationship with stage is sometimes evident, with minor peaks in specific conductivity following some increases in stage.




Figure 3

- The dissolved oxygen (**Figure 4**) values ranged from a minimum of 9.83 mg/L to a maximum of 13.59 mg/L over the deployment period; with the percent saturation ranging between 90.2 and 100.9.
- Dissolved oxygen (mg/L) is generally inversely proportional to water temperature.
- Throughout the deployment period dissolved oxygen values consistently fell above the upper limit recommended by CCME *Canadian Water Quality Guidelines for the Protection of Aquatic Life* (cold water/other life stages above 6.5 mg/L; cold water/early life stages above 9.5 mg/L).
- Based upon the fact that Dissolved Oxygen % Saturation had minimal change over the deployment period, we can be confident that the Dissolved Oxygen mg/L values are accurate.




Figure 4

- The turbidity values (**Figure 5**) ranged from a minimum of 0.0 NTU to a maximum of 14.9 NTU.
- Turbidity was minimal during most of this deployment period, with only six minor and short term events recorded. It is likely that these readings were caused by natural in-stream debris or air bubbles passing near the sensor.
- Turbidity readings of this frequency, intensity and duration are normal.




Figure 5

- The stage or water level ranged from a minimum of 0.97 m to a maximum of 1.25 m. The flow or discharge ranged from a minimum of $0.10 \text{ m}^3/\text{s}$ to a maximum of $2.06 \text{ m}^3/\text{s}$ (**Figure 6**).
- The increase in stage and flow is resultant from precipitation/runoff events.
- Stream stage and flow are within normal ranges.




Figure 6

Prepared by:

Robert Wight Environmental Scientist Water Resources Management Division Department of Environment and Conservation

Tel: 709-292-4280 Fax: 709-292-4365

e-mail: robertwight@gov.nl.ca