

	GOVERNMENT OF NEWFOUNDLAND AND LABRADOR Department of Transportation and Infrastructure	<b>BRIDGE INSPECTION REPORT</b> <b>B10292015-14</b>	
<b>Date:</b> 10/1/2015	<b>Inspected By:</b> Rodger Hussey	<b>Category:</b> Eng. - Engineering	
<b>BRIDGE INFORMATION</b>			
<b>Site:</b>	1-089 - HEAVY TREE ROAD OVERPASS'S (EAST & WEST)		
<b>Route:</b>		<b>Overall Length:</b>	30.8 m
<b>Year Built:</b>	1971	<b>Est:</b> No	<b>Overall Width:</b> 13 m
<b>Year Last Rehab.:</b>	2001	<b>Est:</b> No	<b>Roadway Width:</b> 11 m
<b>Region:</b>	AVALON PENINSULA		<b>Sidewalk Width:</b> 0 m
<b>Jurisdiction:</b>	Provincial		<b>Clearance to R.D. or N.W.L.:</b> 5.5 m
<b>Type of Structure:</b>	13 - Other		<b>Max Depth of N.W.L.:</b> 0 m
<b>Purpose of Structure:</b>	01 - Highway Grade Separation		<b>Spans:</b>
<b>Type of Handrail:</b>	01 - Aluminum Rail		<u>Span No.:</u> <u>Length</u> <u>Span No.:</u> <u>Length</u>
<b>Roadway Surface:</b>	02 - Asphalt		1            18.3    4            0
<b>Alignment Vertical:</b>	01 - Good		2            0            5            0
<b>Alignment Horizontal:</b>	01 - Good		3            0            6            0
<b>Restrictions:</b>	No		
<b>BRIDGE PHOTOS</b>			
			
<b>SUBSTRUCTURE</b>			
<b>Condition:</b>	F2 - Fair	<b>Bearings:</b>	I - Inapplicable
		<b>Bearing Seat:</b>	I - Inapplicable
<b>Comments:</b>	Minor cracking throughout abutment walls and headwalls; Spalling at exterior face of back wall (Multiple locations).		
<b>SUPERSTRUCTURE</b>			
<b>Condition:</b>	F2 - Fair	<b>Expansion Joints:</b>	I - Inapplicable
<b>Comments:</b>	Minor/moderate cracking along exterior face of reinforced slab; Cover not achieved on underside of bridge deck, small areas of exposed reinforcement and rebar chairs, minor corrosion to exposed reinforcement.		
<b>DECK</b>			
<b>Condition:</b>	F2 - Fair	<b>Curbs:</b>	F2 - Fair

<b>Hand Rail:</b>	G - Good	<b>Roadway Condition:</b>	F2 - Fair
<b>Approach Rail:</b>	F2 - Fair		
<b>Comments:</b>	Large pothole in westbound lane; Minor rutting and asphalt stripping in westbound; Minor rutting and several small potholes in eastbound lane.		
<b>HYDROLOGY</b>			
<b>Water Velocity:</b>	0 m/s	<b>Ice Problem:</b>	NA - Not Applicable
<b>Water Depth:</b>	0 m	<b>Scour Problem:</b>	NA - Not Applicable
<b>Waterway:</b>	03 - Not Applicable	<b>Debris Problem:</b>	NA - Not Applicable
<b>Comments:</b>			
<b>REPLACEMENT/REHABILITATION</b>			
<b>Next Rehab. Date:</b>	2015	<b>Replacement Year:</b>	2015
<b>Antic. Rehab. Cost:</b>	\$0	<b>Replacement Cost:</b>	\$0
<b>Recommendations:</b>	Patch potholes or repave driving surface; Repair spalling on back wall; Install hazard markers (2).		
<b>OBSERVATIONS</b>			
<b>Overall Condition:</b>	F2 - Fair	<b>Requires Further Inspection:</b>	No
<b>Additional Observations:</b>	Hazard markers missing in westbound lane (2).		
<b>LEGEND:</b>			
<b>Condition Definitions:</b>		<b>Problem Definitions:</b>	
1 - *Good - [discontinued code].	F2 - Fair.	C - Unsafe (Closed to Public).	N - No Problem.
2 - *Fair - [discontinued code].	F1 - Fair.	U - Uninspectable.	P - Possible Problem.
3 - *Poor - [discontinued code].	P3 - Poor.	I - Inapplicable.	K - Known Problem.
4 - *Unsafe - [discontinued code].	P1 - Poor.		NA - Not Applicable.
G - Good.	P - Poor.		
<b>Category Definitions:</b>			
Maint. - Maintenance.			
Eng. - Engineering.			
Office - Bridge Office.			
<b>PHOTO GUIDELINES:</b>			
<b>Inspection Photos:</b>			
Please provide photos using guidelines below:			
<ul style="list-style-type: none"> <li>● Any item which inspector feels should be documented by photograph</li> <li>● All items noted above as being P3, P1, P, or C</li> <li>● Any evidence of known ice, scour, debris, waterway problems</li> </ul>			
<b>INSPECTION PHOTOS</b>			