

	GOVERNMENT OF NEWFOUNDLAND AND LABRADOR Department of Transportation and Infrastructure	<b>BRIDGE INSPECTION REPORT</b> <b>B02132023-3</b>	
<b>Date:</b> 5/6/2022	<b>Inspected By:</b> Mike Fleming	<b>Category:</b> Eng. - Engineering	
<b>BRIDGE INFORMATION</b>			
<b>Site:</b>	TCH-165 - FIRST AVENUE OVERPASS (WESTBOUND)		
<b>Route:</b>		<b>Overall Length:</b>	19.2 m
<b>Year Built:</b>	1998	<b>Est:</b> No	<b>Overall Width:</b> 12.8 m
<b>Year Last Rehab.:</b>		<b>Est:</b> No	<b>Roadway Width:</b> 12.1 m
<b>Region:</b>	WEST COAST/NORTHERN	<b>Sidewalk Width:</b>	0 m
<b>Jurisdiction:</b>	Provincial	<b>Clearance to R.D. or N.W.L.:</b>	5.6 m
<b>Type of Structure:</b>	03 - Reinforced Concrete Beam/Slab	<b>Max Depth of N.W.L.:</b>	0 m
<b>Purpose of Structure:</b>	01 - Highway Grade Separation	<b>Spans:</b>	
<b>Type of Handrail:</b>	05 - Concrete Barrier	<u>Span No.:</u>	<u>Length</u>
<b>Roadway Surface:</b>	02 - Asphalt	<u>Span No.:</u>	<u>Length</u>
<b>Alignment Vertical:</b>	01 - Good	1	14.9
<b>Alignment Horizontal:</b>	01 - Good	2	0
<b>Restrictions:</b>	No	3	0
		4	0
		5	0
		6	0
<b>BRIDGE PHOTOS</b>			
			
<b>SUBSTRUCTURE</b>			
<b>Condition:</b>	G - Good	<b>Bearings:</b>	G - Good
		<b>Bearing Seat:</b>	G - Good
<b>Comments:</b>			
<b>SUPERSTRUCTURE</b>			
<b>Condition:</b>	G - Good	<b>Expansion Joints:</b>	G - Good
<b>Comments:</b>	Expansion Joints are paved over, one section of asphalt over the expansion joint is delaminated and exposing the expansion joint. Minor spalled section on the deck soffit outside edge with light to moderate corrosion on the exposed reinforcement.		
<b>DECK</b>			
<b>Condition:</b>	G - Good	<b>Curbs:</b>	G - Good

<b>Hand Rail:</b>	G - Good	<b>Roadway Condition:</b>	F2 - Fair
<b>Approach Rail:</b>	F2 - Fair		
<b>Comments:</b>	One missing steel snow fence post noted. Minor damage also noted on the approach rail.		
<b>HYDROLOGY</b>			
<b>Water Velocity:</b>	0 m/s	<b>Ice Problem:</b>	N - No Problem
<b>Water Depth:</b>	0 m	<b>Scour Problem:</b>	N - No Problem
<b>Waterway:</b>	03 - Not Applicable	<b>Debris Problem:</b>	N - No Problem
<b>Comments:</b>			
<b>REPLACEMENT/REHABILITATION</b>			
<b>Next Rehab. Date:</b>		<b>Replacement Year:</b>	
<b>Antic. Rehab. Cost:</b>	\$0	<b>Replacement Cost:</b>	\$0
<b>Recommendations:</b>			
<b>OBSERVATIONS</b>			
<b>Overall Condition:</b>	G - Good	<b>Requires Further Inspection:</b>	No
<b>Additional Observations:</b>	Pics on file		
<b>LEGEND:</b>			
<b>Condition Definitions:</b>		<b>Problem Definitions:</b>	
1 - *Good - [discontinued code].	F2 - Fair.	C - Unsafe (Closed to Public).	N - No Problem.
2 - *Fair - [discontinued code].	F1 - Fair.	U - Uninspectable.	P - Possible Problem.
3 - *Poor - [discontinued code].	P3 - Poor.	I - Inapplicable.	K - Known Problem.
4 - *Unsafe - [discontinued code].	P1 - Poor.		NA - Not Applicable.
G - Good.	P - Poor.		
<b>Category Definitions:</b>			
Maint. - Maintenance.			
Eng. - Engineering.			
Office - Bridge Office.			
<b>PHOTO GUIDELINES:</b>			
<b>Inspection Photos:</b>			
Please provide photos using guidelines below:			
<ul style="list-style-type: none"> <li>● Any item which inspector sees should be documented by photograph</li> <li>● All items noted above as being P3, P1, P, or C</li> <li>● Any evidence of known ice, scour, debris, waterway problems</li> </ul>			
<b>INSPECTION PHOTOS</b>			