

	GOVERNMENT OF NEWFOUNDLAND AND LABRADOR Department of Transportation and Infrastructure	<b>BRIDGE INSPECTION REPORT</b> <b>B02062023-1</b>	
<b>Date:</b> 5/2/2022	<b>Inspected By:</b> Mike Fleming	<b>Category:</b> Eng. - Engineering	
<b>BRIDGE INFORMATION</b>			
<b>Site:</b>	TCH-142 - WHITE'S ROAD UNDERPASS		
<b>Route:</b>		<b>Overall Length:</b>	77.4 m
<b>Year Built:</b>	1980	<b>Est: Yes</b>	<b>Overall Width:</b> 12.3 m
<b>Year Last Rehab.:</b>		<b>Est: No</b>	<b>Roadway Width:</b> 10.5 m
<b>Region:</b>	WEST COAST/NORTHERN	<b>Sidewalk Width:</b>	0 m
<b>Jurisdiction:</b>	Provincial	<b>Clearance to R.D. or N.W.L.:</b>	6.3 m
<b>Type of Structure:</b>	05 - Pre-stressed Concrete Slab	<b>Max Depth of N.W.L.:</b>	0 m
<b>Purpose of Structure:</b>	01 - Highway Grade Separation	<b>Spans:</b>	
<b>Type of Handrail:</b>	01 - Aluminum Rail	<u>Span No.:</u>	<u>Length</u>
<b>Roadway Surface:</b>	02 - Asphalt	1	15.3
<b>Alignment Vertical:</b>	01 - Good	2	19.1
<b>Alignment Horizontal:</b>	01 - Good	3	19.1
<b>Restrictions:</b>	No	<b>Span No.:</b>	<b>Length</b>
		4	15.3
		5	0
		6	0
<b>BRIDGE PHOTOS</b>			
			
<b>SUBSTRUCTURE</b>			
<b>Condition:</b>	F1 - Fair	<b>Bearings:</b>	G - Good
		<b>Bearing Seat:</b>	F2 - Fair
<b>Comments:</b>	Columns are deteriorating with some areas of exposed and corroded steel.		
<b>SUPERSTRUCTURE</b>			
<b>Condition:</b>	F1 - Fair	<b>Expansion Joints:</b>	P1 - Poor
<b>Comments:</b>	Expansion Joints damaged, missing steel, deteriorated concrete, and leaking. Moderate spalling and exposed and corroded steel noted on deck soffit.		
<b>DECK</b>			
<b>Condition:</b>	F1 - Fair	<b>Curbs:</b>	P3 - Poor
<b>Hand Rail:</b>	F1 - Fair	<b>Roadway Condition:</b>	P3 - Poor

<b>Approach Rail:</b>	I - Inapplicable		
<b>Comments:</b>	Moderate deterioration of curbs noted. Some light damage noted on handrail. Significant amount of patched potholes adjacent to expansion joints; asphalt on approaches are deteriorating.		
<b>HYDROLOGY</b>			
<b>Water Velocity:</b>	0 m/s	<b>Ice Problem:</b>	NA - Not Applicable
<b>Water Depth:</b>	0 m	<b>Scour Problem:</b>	NA - Not Applicable
<b>Waterway:</b>	03 - Not Applicable	<b>Debris Problem:</b>	NA - Not Applicable
<b>Comments:</b>			
<b>REPLACEMENT/REHABILITATION</b>			
<b>Next Rehab. Date:</b>	2023	<b>Replacement Year:</b>	
<b>Antic. Rehab. Cost:</b>	\$0	<b>Replacement Cost:</b>	\$0
<b>Recommendations:</b>	Install end blocks, approach rail, handrail, expansion joints replace deck drains, repair columns and deck soffitt. Resurface approaches and deck.		
<b>OBSERVATIONS</b>			
<b>Overall Condition:</b>	P3 - Poor	<b>Requires Further Inspection:</b>	No
<b>Additional Observations:</b>	Pics on file		
<b>LEGEND:</b>			
<b>Condition Definitions:</b>		<b>Problem Definitions:</b>	<b>Category Definitions:</b>
1 - *Good - [discontinued code].	F2 - Fair.	C - Unsafe (Closed to Public).	N - No Problem.
2 - *Fair - [discontinued code].	F1 - Fair.	U - Uninspectable.	P - Possible Problem.
3 - *Poor - [discontinued code].	P3 - Poor.	I - Inapplicable.	K - Known Problem.
4 - *Unsafe - [discontinued code].	P1 - Poor.		NA - Not Applicable.
G - Good.	P - Poor.		
<b>PHOTO GUIDELINES:</b>			
<b>Inspection Photos:</b>			
Please provide photos using guidelines below:			
<ul style="list-style-type: none"> <li>● Any item which inspector sees should be documented by photograph</li> <li>● All items noted above as being P3, P1, P, or C</li> <li>● Any evidence of known ice, scour, debris, waterway problems</li> </ul>			
<b>INSPECTION PHOTOS</b>			