



SECTION A-A

SECTION B-B

1. APPROVED SQUARE OR ROUND PRE-CAST UNITS MAY BE USED ON APPROVAL BY THE ENGINEER.
2. POROUS BACK FILL TO BE PLACED MINIMUM 300 ON ALL SIDES.
3. CONCRETE STRENGTH 35MPa AT 28 DAYS.
4. 3-15M HI-BOND BARS BENT AS PER DETAIL, TIES TO BE 15M HI-BOND BARS, 1000 LONG.
5. MAXIMUM DEPTH TO BE REDUCED IF TOPOGRAPHY IS NOT LEVEL.
6. WEEP HOLES SHALL BE PLACE SO THE BOTTOM OF THE WEEPER ON THE INSIDE AND THE TOP OF THE WEEPER ON THE OUTSIDE ARE LEVEL.
7. LADDER RUNGS TO BE 20M HI-BOND BARS, GALVANIZED OR EQUAL.

