

Table of Contents

1. INTRODUCTION	1
2. ACRONYMS AND DEFINITIONS	2
2.1 Acronyms	2
2.2 Definitions	4
3. GENERAL	7
3.1 Buildings Capital Project Delivery	7
3.1.1 Phase 1 - Programming/Pre-Design Phase	7
3.1.2 Phase 2 - Design Phase	7
3.1.3 Phase 3 - Construction Phase	8
3.1.4 Phase 4 - Post Completion Phase	8
3.2 Project Partners	9
3.2.1 Funding Authority	9
3.2.2 Operating Agency / Department	9
3.2.3 Transportation & Works	9
3.2.4 Client Partners	10
3.3 Project Team	10
3.3.1 Design Manager (DM)	10
3.3.2 Construction Manager (CM)	11
3.3.3 Project Consultant / Prime Consultant	11
3.3.4 TW Design Professionals	19
3.3.5 Other TW Personnel	19
3.3.6 Contractor	19
3.4 Correspondence	20
3.5 Meetings	20
3.6 Media and Public Communications	20
3.7 Infrastructure Approval Process	21

3.8	Capital Budget Forecasts	21
3.8.1	Project Estimates	22
3.8.2	Construction Progress Breakdown	22
4.	PHASE 1 - PROGRAMMING / PRE-DESIGN PHASE	23
4.1	Phase 1, Step 1 - Needs Assessment Role Study	23
4.2	Phase 1, Step 2 – Owner’s Project Requirements	23
4.3	Phase 1, Step 3 - Master Program	24
4.3.1	Spatial Program	24
4.3.2	Room Data Sheets	24
4.4	Phase 1, Step 4 - Site Evaluation and Selection	25
4.5	Phase 1, Step 5 - Existing Facility Condition Assessment	25
4.6	Phase 1, Step 6 - Master Plan	25
4.7	Phase 1, Step 7 - Functional Program	26
4.8	Phase 1, Step 8 - Furniture and Equipment Selection	26
4.9	Phase 1, Step 9 - Pre-Design	26
4.10	Phase 1, Step 10 – LEED	27
5.	PHASE 2 – DESIGN PHASE	27
5.1	Design Period Procedures	27
5.1.1	General	27
5.1.2	Design Phase Communications	28
5.1.3	Schedule	29
5.1.4	Cost Control	29
5.1.5	Design Errors and Omissions	29
5.1.6	Approval Requirements	30
5.2	Phase 2, Step 1 - Concept Design	32
5.2.1	General	32
5.2.2	Prime Consultant	33

5.2.3	Site Surveys	33
5.2.4	Geotechnical	36
5.2.5	Structural	37
5.2.6	Architectural	39
5.2.7	Civil	40
5.2.8	Mechanical	41
5.2.9	Electrical	42
5.2.10	LEED®	43
5.2.11	Commissioning	44
5.3	Phase 2, Step 2 – Design Development	45
5.3.1	General	45
5.3.2	Geotechnical	47
5.3.3	Structural	50
5.3.4	Architectural	50
5.3.5	Civil	51
5.3.6	Mechanical	52
5.3.7	Electrical	53
5.3.8	LEED®	55
5.3.9	Commissioning	56
5.4	Phase 2, Step 3 - Detailed Design	56
5.4.1	General	56
5.4.2	Structural	57
5.4.3	Architectural	59
5.4.4	Civil	60
5.4.5	Mechanical	61
5.4.6	Electrical	62
5.4.7	LEED®	63
5.4.8	Commissioning	64
5.5	Phase 2, Step 4 - Contract Documents	65
5.5.1	General	65
5.5.2	Standard Front End Documents	66
5.5.3	Specification of Equipment & Products	67
5.5.4	Scheduling of Construction Work	67
5.5.5	Liquidated Damages	68
5.5.6	Separate Contracts	68

5.5.7	Furnishings & Special Equipment	69
5.5.8	Project Records System	69
5.5.9	Cash Allowances	69
5.5.10	Separate Prices	70
5.5.11	Unit Prices	70
5.5.12	Tender Documents	70
5.5.13	Architectural	71
5.5.14	Civil	71
5.5.15	Structural	72
5.5.16	Mechanical	73
5.5.17	Electrical	74
5.5.18	Constructability Review	75
5.5.19	LEED®	77
5.5.20	Commissioning	77
5.5.21	Safety Specification	78
5.6	Phase 2, Step 5 – Tendering and Contract Award	78
5.6.1	Public Tenders	78
5.6.2	Invited Prices	78
5.6.3	Site Briefings / Viewings	79
5.6.4	Inquiries from Prospective Bidders	79
5.6.5	Preparation of Addenda	80
5.6.6	Substitution Of Material	80
5.6.7	Bid Depository	80
5.6.8	Listing of Major Sub-Contractors and Suppliers	80
5.6.9	Requests for Tender Withdrawal	81
5.6.10	Tender Exceeding Project Budget	81
5.6.11	Tender Analysis, Approval and Award	82
5.6.12	Contract Agreement	82
5.6.13	Construction Document Package	82
5.7	Phase 2, Step 6 - Design Manager to Construction Manager Handover	84
6.	PHASE 3 - CONSTRUCTION PHASE	84
6.1	Construction Phase Procedures	84
6.1.1	Safety	84
6.1.2	Construction Phase Communications	87

6.1.3	REQUIREMENTS PRIOR TO START OF WORK	88
6.1.4	Pre-Construction Meeting	88
6.1.5	Project Status Reporting	89
6.1.6	Request for Information	89
6.1.7	Change Orders	90
6.1.8	Shop Drawings	92
6.1.9	Payment of Contractor's Invoices	93
6.1.10	Owner's Right To Do Work	95
6.1.11	Owner's Right To Terminate the Contract	95
6.1.12	Environmental Considerations During Construction	95
6.1.13	Dispute Resolution and Management	96
6.1.14	Consultant Services - Additional Services	97
6.1.15	Quality Control & Inspection Services	97
6.1.16	Permits	102
6.2	Phase 3, Step 1 - Contract Administration	102
6.2.1	Consultants Role in Contract Administration	102
6.3	Phase 2, Step 2 - Commissioning	105
6.3.1	Installation Verification	107
6.3.2	Performance Verification	107
6.3.3	Facility Start-up	108
6.4	Phase 3, Step 3 - Training and Education	108
6.5	Phase 3, Step 4 - Warranties	108
6.6	Phase 3, Step 5 – Operation and Maintenance Manual	109
6.7	Phase 3, Step 6 - Substantial Completion	110
6.8	Phase 3, Step 7 - Final Completion	111
6.8.1	Issuance of Total Performance Certificate	111
7.	PHASE 4 - POST COMPLETION PHASE	113
7.1	Phase 4, Step 1 - Contract Close Out Documentation	113
7.1.1	Project Record Drawings	113
7.1.2	Project Factsheet	114
7.1.3	Insurance Preamble	114

7.1.4	Building Inventory Data Sheet _____	116
7.1.5	Government Building Data Sheet _____	116
7.1.6	LEED® _____	117
7.2	Phase 4, Step 2 - Contractor Performance Evaluation _____	118
7.2.1	General _____	118
7.2.2	Performance Rating Methodology _____	118
7.2.3	Interpretation of Rating _____	120
7.2.4	Completion of the Evaluation Report _____	120
7.2.5	Suspension of Bidding Privileges _____	120
7.2.6	Reinstatement of Bidding Privileges _____	121
7.2.7	Contractor's Appeal _____	121
7.2.8	Confidentiality of Information _____	121
7.3	Phase 4, Step 3 - Handover _____	122
7.4	Phase 4, Step 4 - Completion of Work Under Warranty _____	123
7.5	Phase 4, Step 5 – Post Occupancy Evaluation _____	124
8.	DOCUMENTATION STANDARDS _____	125
8.1	Copyright _____	125
8.2	Sealing and Signing of Documents _____	125
8.3	Systems Measurement and Metric Content _____	125
8.4	Technical Document Submittals _____	125
8.4.1	Hard Copies _____	126
8.4.2	Electronic Submission _____	127
8.5	Drawing Number and Signature Procedures _____	127
8.6	Production of Drawings _____	129
8.6.1	Drawing Cover Sheets _____	129
8.6.2	Drawing Sheets _____	129
8.6.3	Lines and Lettering by Object Line Weight _____	129
8.6.4	Drafting Scales _____	130
8.6.5	Dimensioning _____	131

8.6.6	Cad Layers _____	131
8.6.7	X-Refs and Purging _____	132
8.7	Specification _____	132
8.8	Drawing Changes During/After Tendering _____	132
9.	CIVIL - TECHNICAL _____	133
9.1	Regulations _____	133
9.1.1	Codes and Standards _____	133
9.1.2	Authorities having Jurisdiction _____	133
9.2	Site Investigation _____	133
9.3	Codes and Standards _____	134
9.4	Submissions _____	134
9.5	Design Flow _____	134
9.6	Pipes _____	135
9.7	Valves _____	135
9.8	Fire Protection _____	135
9.9	Sanitary & Storm Sewers _____	136
9.9.1	General _____	136
9.9.2	Design of Sanitary Sewers _____	136
9.9.3	Design of Storm Sewer System _____	137
9.9.4	Manholes and Catch Basins _____	137
9.9.5	Sewage Forcemains _____	137
9.9.6	Sewage Lift Stations _____	138
9.9.7	Bedding and Backfilling _____	138
9.9.8	Inspection and Testing _____	138
9.10	Site Grading and Surface Drainage _____	139
9.10.1	General Requirements _____	139
9.10.2	Side Slopes, Ditches and Back Slopes _____	139
9.10.3	Culverts _____	140

9.10.4	Drainage Appurtenances	140
9.11	Subsurface Drainage	140
9.12	Pavements - Roads, Parking Lots and Sidewalks	141
9.12.1	Intersections	141
9.12.2	Roads Design Criteria and Requirements	141
9.12.3	Parking Lots	142
9.12.4	Sidewalks	143
9.13	Planting Design	144
9.13.1	General Requirements	144
9.13.2	Trees & Shrubs	144
9.13.3	Topsoil, Lawns and Plant Materials	144
9.14	Fencing and Guide Rails	145
9.14.1	Fencing	145
9.14.2	Guide Rails	145
9.15	Supply and Waste Handling	145
9.16	Site Furnishings	145
9.17	Signs	146
9.17.1	Traffic Control Signs	146
9.17.2	Exterior Way finding and Informational Signs	146
9.17.3	Project Signs	146
9.18	Flagpoles	146
9.19	Drawing Contents	146
9.19.1	Existing Conditions Drawings	146
9.19.2	Grading Drawings	147
9.19.3	Site Services Drawings	147
9.19.4	Landscaping Drawings	148
9.19.5	Pavement Plan	148
9.20	Demolition	148
9.20.1	General Requirements	148
9.20.2	Demolition Plan	149

9.20.3	Public Protection	149
10.	STRUCTURAL - TECHNICAL	150
10.1	Regulations	150
10.1.1	Codes and Standards	150
10.1.2	Authorities Having Jurisdiction	150
10.2	Submission	150
10.3	Structural Steel	150
10.4	Structural Lumber	150
10.5	Reinforced Concrete	151
10.6	Engineered Masonry	151
11.	ARCHITECTURAL - TECHNICAL	152
11.1	Regulations	152
11.1.1	Codes and Standards	152
11.1.2	Authorities having Jurisdiction	152
11.2	Facility Planning	152
11.2.1	Net Area	152
11.2.2	Building Gross Area Measurement	152
11.2.3	Department Gross Area	154
11.2.4	Space Audit	154
11.2.5	Net to Gross Ratio	155
11.2.6	Flexibility	155
11.2.7	Appropriate Spaces	155
11.2.8	Circulation	156
11.2.9	Circulation Routes	156
11.2.10	Vertical Circulation	156
11.2.11	Horizontal Circulation	156
11.2.12	Entrances and Exits	157
11.2.13	Barrier Free Design	157
11.2.14	Sustainable Development	157

11.2.15	Environmental Health	158
11.3	Building Envelope	158
11.3.1	Flat Roofs	158
11.3.2	Sloped Roofs	158
11.3.3	Roof Repair - Replacement	159
11.3.4	Skylights	160
11.3.5	Thermal Insulation	160
11.3.6	Air Barriers	161
11.3.7	Vapor Barriers	161
11.3.8	Rain Screen Walls	162
11.3.9	Wood Cladding	162
11.3.10	Vinyl Cladding	163
11.3.11	Metal Cladding	163
11.3.12	Masonry Veneer Cladding	163
11.3.13	Sealants	163
11.3.14	Exterior Wall Framing	164
11.3.15	Curtain Walls	164
11.3.16	Exterior Doors	165
11.3.17	Windows	166
11.3.18	Building Form	167
11.3.19	Snow Drifting	167
11.4	Architectural Interior Finishes	167
11.4.1	Wall Coverings	167
11.4.2	Ceramic Wall Tiles	168
11.4.3	Paints	168
11.4.4	Other Wall Finishes	168
11.4.5	Carpets	168
11.4.6	Ceramic Floor Tiles	169
11.4.7	Quarry Tiles	169
11.4.8	Vinyl Composite Tiles	169
11.4.9	Resilient Sheet Tile Flooring	169
11.4.10	Rubber Flooring	170
11.4.11	Linoleum	170
11.4.12	Vinyl Base	170
11.4.13	Natural Stone	170
11.4.14	Sport Flooring	170

11.4.15	Gypsum Board Ceiling Finishes	171
11.4.16	Acoustical Tile Ceilings	171
11.4.17	Finish Schedule	171
11.4.18	Interior Doors	172
11.4.19	Firewalls	172
11.5	Interior Design	173
11.5.1	Fit-up Layouts	173
11.5.2	Color Schemes	173
11.5.3	Systems Furniture	173
11.5.4	Office Furnishings	173
11.5.5	Window Treatments	174
11.5.6	Planters and Plants	174
11.5.7	Artwork	174
11.5.8	Barrier Free Design	174
12.	MECHANICAL - TECHNICAL	176
12.1	Regulations	176
12.1.1	Codes and Standards	176
12.1.2	Authorities Having Jurisdiction	176
12.2	Submission Requirements	177
12.2.1	Submission Requirements	177
12.3	Plumbing	177
12.3.1	Domestic Water Supply (Hot and Cold)	177
12.3.2	Drainage, Waste and Venting	177
12.3.3	Plumbing Fixtures	178
12.4	Fire Protection	179
12.4.1	Sprinkler and Standpipe Systems	179
12.4.2	Clean Agent Extinguishing System	180
12.4.3	Wet Chemical Extinguishing Systems	180
12.4.4	Portable Fire Extinguishers	180
12.5	Heating	180
12.5.1	General	180
12.5.2	Design Temperatures (heating load)	180

12.5.3	Zoning	181
12.5.4	Forced Air Systems	181
12.5.5	Hydronic Heating Systems	182
12.5.6	Fuel Tanks and Piping	184
12.5.7	Heat Pump Systems - Unitary Water-Loop	186
12.5.8	Ground Source Heat Pumps	187
12.6	Ventilation And Air Conditioning	187
12.6.1	Ventilation	187
12.6.2	Variable Air Volume (VAV) Systems	187
12.6.3	Design Temperatures (Cooling Load)	188
12.6.4	Zoning	189
12.6.5	Humidity	190
12.6.6	Acoustics	190
12.6.7	Equipment and Components	190
12.6.8	Equipment Access	192
12.6.9	Air Distribution Systems	193
12.6.10	Air Filtration	193
12.6.11	Humidifiers	193
12.7	Control Systems For HVAC	194
12.7.1	General	194
12.7.2	Hardware	194
12.7.3	Software	195
12.8	Energy Life Cycle Costs	195
13.	ELECTRICAL - TECHNICAL	197
13.1	General Requirements	197
13.2	Regulations	197
13.2.1	Codes and Standards	197
13.2.2	Authorities Having Jurisdiction	198
13.3	Submission Requirements	198
13.3.1	Submissions	198
13.4	Service and Distribution	199

13.4.1	Incoming Electrical Services	199
13.4.2	Capacity of Electrical Service	199
13.4.3	Electrical Rooms	200
13.4.4	Switchgear Assemblies	200
13.4.5	Transformer Types	201
13.4.6	Wiring Methods	201
13.4.7	Panelboards	202
13.4.8	Ceiling Distribution	202
13.5	Lighting	203
13.5.1	Lighting - General	203
13.5.2	Lighting Fixtures	205
13.5.3	Exterior Lighting	205
13.5.4	Emergency Lighting	206
13.5.5	Exit Signs	206
13.6	Electric Heating	207
13.7	Systems	207
13.7.1	Intercommunication Systems	207
13.7.2	Fire Alarm System	207
13.7.3	Intrusion Alarm and Remote Monitoring	208
13.7.4	Telecommunications System (Telephone and Data)	208
13.7.5	Clocks	209
13.8	Motors and Controls	209
13.8.1	Motor Controls	209
13.8.2	Motor Control Centers	210
13.8.3	Motor Equipment Feeders	210
13.9	Lightning Protection	211
13.10	Control Systems	211
13.11	Emergency Generator	211
13.12	Central Control Consoles	211
13.13	Power Quality	212

13.14	Grounding	212
13.15	Sustainability Management System (SMS) Public Interface	213
14.	BUILD BETTER BUILDINGS POLICY AND LEED	214
14.1	Build Better Building Policy	214
14.2	LEED®	214
14.3	LEED® Requirements	214
15.	REFERENCE FORMS AND DOCUMENTS	216